

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATED, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Lease or Property Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
WALLACE 7.5'
Well Location
GRANT
District
WETZEL
County
7379
Well No.
CONSOLIDATION COAL COMPANY
Farm

STATE INSPECTOR SUPERVISING PLUGGING 

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MICHAEL CAMPBELL and KEVIN WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 12th day of September, 2014 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned 12 1/2" hole from Surface to 331'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 331' to 1392'. Reduced hole to 7 7/8". Cleaned 7 7/8" hole from 1392' to 1516'. Tagged solid plug at 1516'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 1150' to 1157'. Possible small junk remains through the coal seam from 1150' to 1157'.		16" Conductor	0'	20'
Cemented hole from 1516' back to surface as follows: From 1516' to 1357' with 60 sacks of Expandable Cement. From 1357' to 1050' with 170 sacks of Thixotropic Cement with dye. From 1050' back to the Surface with 510 sacks of Expandable Cement. Cement did circulate at the surface. Left 20' of 16" Conductor Casing in the hole from Surface to 20'.				
Coal Seams		Description of Monument		
Pittsburgh	(1096' - 1103')	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

RECEIVED
Office of Oil and Gas
NOV 17 2014
WV Department of
Environmental Protection

... and that the work of plugging and filling said well was completed on the 26th day of September, 2014

And further deponents saith not.



Michael Campbell


Kevin S. Wright

Sworn to and subscribed before me this 27 day of October 2014


Kara Beth Forst
Notary Public

My commission expires: 11/4/23



Permit No. 47-103-03009-P
Well No. 7379