





1046

STATE OF WEST VIRGINIA  
DEPARTMENT OF MINES  
OIL AND GAS DIVISION

WELL RECORD

Permit No. 597-A


Oil or Gas Well Oil  
(KIND)

Company The Interstate Pipe & Supply Company  
Address P. O. Box 611, Marietta, Ohio  
Farm Abe Ice Acres 37 1/2  
Location (waters) Sams Run  
Well No. 1 Elev. 1189.27  
District Grant County Wetzel  
The surface of tract is owned in fee by Robinson Improvement Co  
Address The Plains, Va.  
Mineral rights are owned by State of West Virginia  
Address Charleston, W.Va.  
Drilling commenced June 24, 1902  
Drilling completed September 13, 1902  
Date Shot '04, '09, '13 From 3115 To 3124  
With \_\_\_\_\_  
Open Flow /10ths Water in \_\_\_\_\_ Inch  
/10ths Merc. in \_\_\_\_\_ Inch  
Volume \_\_\_\_\_ Cu. Ft.  
Rock Pressure \_\_\_\_\_ lbs. \_\_\_\_\_ hrs.  
Oil \_\_\_\_\_ bbls., 1st 24 hrs.  
Fresh water \_\_\_\_\_ feet \_\_\_\_\_ feet  
Salt water \_\_\_\_\_ feet \_\_\_\_\_ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
18			
	318	none	Size of
8 1/4	1512	none	
6%	1990	1990	Depth set
5 3/16	2456	2456	
3			Perf. top
2			Perf. bottom
Liners Used			Perf. top
4x4 1/2	182	182	Perf. bottom

CASING CEMENTED \_\_\_\_\_ SIZE \_\_\_\_\_ No. Ft. \_\_\_\_\_ Dat \_\_\_\_\_  
COAL WAS ENCOUNTERED AT 1050 FEET 60 INCHES  
\_\_\_\_\_ FEET \_\_\_\_\_ INCHES \_\_\_\_\_ FEET \_\_\_\_\_ INCHES  
\_\_\_\_\_ FEET \_\_\_\_\_ INCHES \_\_\_\_\_ FEET \_\_\_\_\_ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Conductor			0	16			
Coal			1050	1055			
Dunkard Sand			1460	1480			
Salt Sand			1896	2060			
Pencil Cave			2250	2255			
Big Injun			2325	2425			
Fifty Foot			2900	2925			
Stray Sand			3116	3141			
1st Pay			3126				
Gordon Sand			3149				
Total Depth				3169			
<p>March 11, 1919, 182' of 4 x 4 1/2 F.S. Liner hung on 4 x 5-3/16" Callahan Cave Packer set at 2445'.</p>							



Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks

Date August 7, 194 7

APPROVED THE INTERSTATE PIPE & SUPPLY CO., Owner

By H. H. Berens  
(Title)