

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Brame Higgins Operator Well No.: 7365

LOCATION: Elevation: 1293.87' Quadrangle: Wallace, WV 7.5'
District: Grant County: Wetzel
Latitude: 39.494558 Feet South of 39 Deg. 29 Min. 40.408 Sec.
Longitude: -80.497945 Feet West of -80 Deg. 29 Min. 52.602 Sec.

Well Type: OIL _____ GAS X

Company Consolidation Coal Co. Coal Operator Consolidation Coal Co.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Coal Operator _____
Agent David Roddy or Owner _____
Permit Issued Date 05/20/2019

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 9th day of October, 2020, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye	1406'	988'		
Expandable Cement	988'	Surface		
8 5/8" Casing	370'	383'	0'	13'
16" Conductor Pipe	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 19th day of October, 2020.


And further deponents saith not. Matthew A. Yearsley

Kevin S. Wright

Sworn and subscribe before me this 26th day of Oct, 2020

My commission expires: 09/15/22

[Signature]
Notary Public



Affidavit reviewed by the Office of Oil and Gas: Derek M. Haught Title: Oil & Gas Inspector 06/04/2021

Plugging Report for MSHA

Well Number: 7365

Mine: Harrison County Mine

Surface

Permit Number: 47-103-03303

Date Clean Out Started: 10/9/2020

Date Well Bore Plugged: 10/19/2020

Pittsburgh Coal Seam: 1189 ft. To 1195 ft.

Plugs:	From	To	Type of Cement
	<u>1406'</u>	<u>988'</u>	<u>Thixotropic Cement w/ Green Dye</u>
	<u>988'</u>	<u>Surface</u>	<u>Expandable Cement</u>

Top of 16" Conductor at Surface
 Bottom of 16" Conductor at 20'
 Top of 8 5/8" Casing at 370'
 Bottom of 8 5/8" Casing at 383'

Expandable Cement

Casing Remaining in Well Bore

Thix Top: 988'

	Top	Bottom	Left	Pulled
Sucker Rods				
2 3/8" tubing				
4 1/2" casing				
7" casing				
7" fiberglass				
8 5/8" casing	370'	383'	13'	0'
10 3/4" casing				
16" Conductor	Surface	20'	20'	0'

Thixotropic Cement w/ Green Dye

1189' - 1195'

Pittsburgh Coal

Cement:

Expandable	<u>510</u>	sacks
Thixotropic	<u>240</u>	sacks
Econofill		sacks
Mud Flush	<u>1000</u>	gal
Other		
Est. Top Thix		ft
Did Cement Circ.	<u>Yes</u>	

Comments:

Caving: Extreme Moderate **Normal**
 Lost Circulation: Extreme Moderate **Normal**
 Difficulty in Removing Casing: **Extreme** Moderate Normal
 Debris in Well Bore: **Wood** **Steel** Other: _____

Thixotropic Cement w/ Green Dye

Surface Elevation (Surveyed)	<u>1294'</u>
Bottom of Coal Structure (Map)	<u>105'</u>
Difference	<u>1189'</u>

Thix Bottom: 1406'

Total Depth: 1406'

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
ROBERT P. & RANDALL B. NICHOLS
Lease or Property Owner
6753 N. RIDGE RD. MADISON, OH 44057
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
WALLACE, WV 7.5'
Well Location
GRANT
District
WETZEL
County
7365
Well No.
BRAME HIGGINS
Farm

STATE INSPECTOR SUPERVISING PLUGGING Derek M. Haught

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 9th day of October, 2020 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleansed the hole with a 12 1/4" bit from the surface to the top of the 8 5/8" casing at 370'. Reduced hole to 7 7/8" at 370'. Cleansed the hole with a 7 7/8" bit from 370' to 1406'. Tagged plug at 1406'. Left 13' of 8 5/8" casing in the hole from 370' to 383'. Cleansed a 7 7/8" hole through the Pittsburgh Coal (1189 - 1195'). Left 20' of 16" conductor pipe in the hole from 20' to surface.		8 5/8" Casing	0'	13'
		16" Conductor	20'	20'
Cemented the hole from 1406' to surface as follows: From 1406' to 988' with 240 sacks of Thixotropic Cement with Green Dye. Tagged the cement plug at 988'. From 988' to surface with 510 sacks of Expandable Cement. Cement did circulate at surface. A total of 750 sacks of cement were used to fill the hole from 1406' to surface.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	1189' - 1195'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 19th day of October, 2020

And further deponents saith not.



Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

Sworn to and subscribed before me this 26th day of Oct, 2020

[Signature]

06/04/2021

Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03303
Well No. 7365
Latitude: 39° 29' 40.408"N
Longitude: -80° 29' 52.602"W