

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Geo. N. Stockdale Operator Well No.: 8276

LOCATION: Elevation: 1341.30' Quadrangle: Hundred WV, PA 7.5'
District: Church County: Wetzel
Latitude: _____ Feet South of 39 Deg. 38 Min. 59.74 Sec.
Longitude: _____ Feet West of -80 Deg. 24 Min. 58.43 Sec.

Well Type: OIL X GAS _____

Company Consolidation Coal Co. Coal Operator Consolidation Coal Co.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Coal Operator _____
Agent David Roddy or Owner _____
Permit Issued Date 7/24/2019 _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 4th day of February, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye	1510'	986'		
Expandable Cement	986'	Surface		
8 5/8" Casing	1207'	Unknown	308'	Unknown
16" Conductor Pipe	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 23rd day of February, 2021.

And further deponents saith not. Kevin S. Wright
Matthew A. Yearsley



Sworn and subscribe before me this 18th day of Mar, 2021

My commission expires: 09/15/22 [Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: 3/17/21 Inspector

09/13/2024

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
ALBERT E. & BRENDA S. REYNOLDS
Lease or Property Owner
81 POGUE RUN ROAD BURTON, WV 26562
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
HUNDRED WV, PA 7.5'
Well Location
CHURCH
District
WETZEL
County
8276
Well No.
GEO. N. STOCKDALE
Farm

STATE INSPECTOR SUPERVISING PLUGGING

Bryan Harris

3/17/21

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

KEVIN S. WRIGHT and MATTHEW A. YEARSLEY being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 4th day of February, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned hole with a 12 1/4" bit from the surface to 332'. Reduced hole to 9 7/8" at 332'. Cleaned hole with a 9 7/8" bit from 332' to the top of the 8 5/8" casing at 899'. Reduced hole to 7 7/8" at 889'. Cleaned a 7 7/8" hole through the 8 5/8" casing from 899' to 1510'. Removed 308' of 8 5/8" casing from 899' to 1207'. Attempted to remove the remaining 8 5/8" casing from 1207' by pulling 150% of the string weight. All attempts to remove remaining 8 5/8" casing from 1207' were unsuccessful. Left an unknown amount of 8 5/8" casing in the hole from 1207' to an unknown depth. Cut remaining 8 5/8" casing at the following depths, 1396', 1342', 1292' and 1242'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam from 1186' to 1192'. Left 20' of 16" conductor pipe in the hole from the surface to 20'. Cemented the hole from 1510' to surface as follows: From 1510' to 986' with 215 sacks of Thixotropic Cement with Green Dye. Tagged cement plug at 986'. Cemented hole from 986' to surface' with 475 sacks of Expandable Cement. Cement did circulate at surface. A total of 690 sacks of cement were used to cement the hole from 1510' to surface.	8 5/8" Casing 16" Conductor	308' 0'	Unknown 20'	
Coal Seams	Description of Monument			
<u>Pittsburgh</u>	1186' – 1192' 77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.			

... and that the work of plugging and filling said well was completed on the 23rd day of February, 2021

And further deponents saith not.



Kevin S. Wright

Kevin S. Wright

Matthew A. Yearsley

Matthew A. Yearsley

Sworn to and subscribed before me this 18th day of Mar, 2021

[Signature] 09/13/2024
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03318
Well No. 8276
Latitude: 39° 38' 59.74" N
Longitude: -80° 24' 58.43" W