

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Sara A. M. Lemley Operator Well No.: 4663

LOCATION: Elevation: 1241.87 Quadrangle: Hundred WV, PA 7.5'
District: Church County: Wetzel
Latitude: _____ Feet South of 39 Deg. 38 Min. 29.382 Sec.
Longitude: _____ Feet West of 80 Deg. 23 Min. 54.42 Sec.

Well Type: OIL _____ GAS X

Company Consolidation Coal Co. Coal Operator 1 Bridge Street Monongah, WV 26554
or Owner _____
Agent David Roddy Coal Operator _____
or Owner _____
Permit Issued Date 09/10/2019

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Kevin S. Wright and Matthew A. Yearsley being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 18th day of May, 2020, and the well was plugged and filled in the following manner:

| TYPE | FROM | TO | PIPE REMOVED | LEFT |
|--------------------------|---------|---------|--------------|---------|
| Thixotropic w/ Green Dye | 1323' | 847' | | |
| Expandable Cement | 847' | Surface | | |
| 2 3/8" Tubing | | | 23' | 0' |
| 8 5/8" casing | 764' | Unknown | 36' | Unknown |
| 16" Conductor | Surface | 20' | 0 | 20' |
| | | | | |

Description of monument: 77' of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 5th day of June, 2020.

And further deponents saith not. Kevin S. Wright
Matthew A. Yearsley



Sworn and subscribe before me this 15th day of Jun, 2020
My commission expires: 09/15/22
Thomas J. Sullivan
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Derek M. Haught Title: Oil & Gas Inspector

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
ALBERT B. YOST (C/O FRANKLIN YOST)
Lease or Property Owner
P.O. BOX 910 HUNDRED, WV 26575
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
HUNDRED WV, PA 7.5'
Well Location
CHURCH
District
WETZEL
County
4663
Well No.
SARAH A. M. LEMLEY
Farm

STATE INSPECTOR SUPERVISING PLUGGING Derek M. Haught

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

KEVIN S. WRIGHT and MATTHEW A. YEARSLEY being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 18TH day of May, 2020 and that the well was plugged in the following manner:

| Sand or Zone Record | Filling Material | Casing/Tubing Size | Casing Pulled | Casing Left In |
|---|---|---|----------------------|----------------|
| Formation | | | | |
| Removed 23' of 2 3/8" Tubing from surface to 23'. Cleaned 12 1/4" hole from surface to 224'. Reduced hole to 9 7/8" at 224'. Cleaned 9 7/8" hole from 224' to 728'. Tagged 8 5/8" casing at 728'. Reduced hole to 6 1/4" at 728'. Cleaned out 8 5/8" casing with 6 1/4" bit from 728' to 1191'. Reduced hole to 4 3/4" at 1191'. Cleaned 4 3/4" hole from 1191' to 1323'. Tagged plug at 1323'. Removed 36' of 8 5/8" casing from 728' to 764'. Left an unknown amount of 8 5/8" casing in the hole from 764' to an unknown depth. The remaining 8 5/8" casing had pre-existing rips in it from 1288' to 1284', 1202' to 1184', 1072' to 1062', 1029' to 1025', 923' to 911' and 829' to 825'. Additional cuts were made in the 8 5/8" casing at the following depths; 1179', 1129', 1089', 1084', 1079', 1077', 1075', 1022', 972' and 816'. The remaining 8 5/8" casing was perforated with 4 shots at each of the following depths; 1279', 1229', 1089', 1084', 1079', 1077', 1075', 1072', 1067' and 1062'. Left 8 5/8" through the Pittsburgh Coal Seam from 1072' to 1079'. Attempted to pull remaining 8 5/8" casing by pulling 150% of the string weight. All attempts to remove the 8 5/8" casing were unsuccessful. Left 20' of 16" conductor pipe in the hole from 20' to surface. | 2 3/8" Tubing 8 5/8" Casing 16" Conductor | 23' 36' 0' | 0' Unknown 20' | |
| <u>Cemented hole from 1323' to surface as follows:</u> From 1323' to 847' with 135 sacks of Thixotropic Cement w/ green dye. From 847' to surface with 430 sacks of Expandable Cement. Cement did circulate at surface. | | | | |
| Coal Seams | | Description of Monument | | |
| Pittsburgh | 1072' - 1079' | 7" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level. | | |

... and that the work of plugging and filling said well was completed on the 5th day of June, 2020

And further deponents saith not.

Kevin S. Wright

Kevin S. Wright

Matthew A. Yearsley

Matthew A. Yearsley

Sworn to and subscribed before me this 15th day of Jun, 2020

[Signature]

Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03321
Well No. 4663
Latitude_DD: 39.641495 N
Longitude_DD: -80.398450W

