

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: P. Edgell Heirs Operator Well No.: 7206

LOCATION: Elevation: 1114.25' Quadrangle: Folsom WV 7.5'  
District: Grant County: Wetzel  
Latitude: 39.492633 Feet South of 39 Deg. 29 Min. 33.5 Sec.  
Longitude: -80.539681 Feet West of -80 Deg. 32 Min. 22.9 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company Consolidation Coal Co. Coal Operator Consolidation Coal Co.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Coal Operator \_\_\_\_\_  
Agent David Roddy or Owner \_\_\_\_\_  
Permit Issued Date 09/25/2019

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 21st day of September, 2020, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye	1181'	701'		
Expandable Cement	701'	Surface		
8 5/8" Casing	1121'	Unknown	286'	Unknown
10 3/4" Casing	380'	756'	0'	376'
16" Conductor Pipe	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 7th day of October, 2020.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 26th day of Oct, 2020  
My commission expires: 09/15/22  
[Signature]  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Derek M. Haught Title: Oil & Gas Inspector 06/04/2021

# Plugging Report for MSHA

Well Number: 7206

Mine: Harrison County Mine

Surface

Permit Nbr: 47-103-03326

Date Clean Out Started: 9/21/2020

Date Well Bore Plugged: 10/7/2020

Pittsburgh Coal Seam: 916 ft. To 922 ft.

**Plugs:**

From	To	Type of Cement
1181'	701'	Thixotropic Cement w/ Green Dye
701'	Surface	Expandable Cement

**Casing Remaining in Well Bore**

Thix Top: 701'

	Top	Bottom	Left	Pulled
Sucker Rods				
2 3/8" tubing				
4 1/2" casing				
7" casing				
7" fiberglass				
8 5/8" casing	1122'	Unknown	Unknown	286'
10 3/4" casing	380'	756'	376'	0'
16" Conductor	Surface	20'	20'	0'

Expandable Cement

Top of 16" Conductor at Surface

Bottom of 16" Conductor at 20'

Top of 10 3/4" Casing at 380'

Bottom of 10 3/4" Casing at 756'

Thixotropic Cement w/  
Green Dye

916' -  
922"

Pittsburgh Coal

Thixotropic Cement w/  
Green Dye

Top of 8 5/8" Casing at 1121'

Bottom of 8 5/8" Casing is Unknown

**Cement:**

Expandable	<u>410</u>	sacks
Thixotropic	<u>250</u>	sacks
Econofill		sacks
Mud Flush	<u>1000</u>	gal
Other		
Est. Top Thix		ft
Did Cement Circ.	<u>Yes</u>	

**Comments:**

Caving: Extreme Moderate **Normal**

Lost Circulation: Extreme **Moderate** Normal

Difficulty in Removing Casing: Extreme **Moderate** Normal

Debris in Well Bore: **Wood** **Steel** Other: \_\_\_\_\_

Surface Elevation (Surveyed)	<u>1114'</u>
Bottom of Coal Structure (Map)	<u>192'</u>
Difference	<u>922'</u>

Thix Bottom: 1181'

**Total Depth: 1181'**

06/04/2021

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
SHELIA JEAN & JOHN CHARLES TEDROW  
Lease or Property Owner  
199 STOUT RUN RD. SMITHFIELD, WV 26437  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
FOLSOM, WV 7.5'  
Well Location  
GRANT  
District  
WETZEL  
County  
7206  
Well No.  
P. EDGELL HIERS  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Derek M. Haught

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 21<sup>st</sup> day of September, 2020 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleansed hole with a 12 1/4" bit from the surface to the top of the 10 3/4" casing at 380'. Reduced hole to 9 7/8" at 380'. Cleaned hole with a 9 7/8" bit from 357' to the top of the 8 5/8" casing at 836'. Reduced hole to 7 7/8" at 836'. Cleaned hole with a 7 7/8" bit from 836' to 1181'. Tagged plug at 1181'. Removed 286' of 8 5/8" casing from 836' to 1122'. Attempted to remove additional 8 5/8" casing by pulling 150% of the string weight but all attempts were unsuccessful. Left an unknown amount of 8 5/8" casing in the hole from 1121' to an unknown depth. Left 376' of 10 3/4" casing in the hole from 380' to 756'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam from 916' to 922'.		8 5/8" Casing	286'	Unknown
		10 3/4" Casing	0'	376'
		16" Conductor	20'	20'
<b>Cemented the hole from 1181' to surface as follows:</b>				
From 1181' to 701' with 250 sacks of Thixotropic Cement with Green Dye. Tagged the cement plug at 701'. From 701' to surface with 410 sacks of Expandable Cement. Cement did circulate at surface. A total of 660 sacks of cement were used to cement the hole from 1181' to surface. Left 20' of 16" conductor in the hole from 20' to surface.				
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	916' - 922'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 7<sup>th</sup> day of October, 2020


And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright



Sworn to and subscribed before me this 26<sup>th</sup> day of Oct, 2020

[Signature] **06/04/2021**  
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03326  
Well No. 7206  
Latitude: 39° 29' 33.5"N  
Longitude: -80° 32' 22.9"W