

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: John Whistler Operator Well No.: 4527

LOCATION: Elevation: 1137.00' Quadrangle: Hundred, WV PA 7.5'
District: Church County: Wetzel
Latitude: _____ Feet South of 39 Deg. 38 Min. 45.06 Sec.
Longitude: _____ Feet West of -80 Deg. 24 Min. 36.69 Sec.

Well Type: OIL X GAS _____

Company Consolidation Coal Co Coal Operator Consolidation Coal Co
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 9/27/2019 or Owner _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 5th day of April, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1256'	793'		
Expandable Cement	793'	Surface		
8 5/8" Casing	1,009	Unknown	0' (Ripped and Cut)	Unknown
16" Conductor	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 15th day of April, 2021.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 11th day of May, 2021

My commission expires: 09/15/22
Thomas J. Sullivan
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector

06/11/2021

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CHARLES EDWARD JR & BETTY BELINDA CUE
Lease or Property Owner
310 POGUE RUN ROAD BURTON, WV 26562
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
HUNDRED, WV, PA 7.5'
Well Location
CHURCH
District
WETZEL
County
4527
Well No.
JOHN WHISTLER
Farm

STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris
AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 5th day of April, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned the hole with a 12 1/4" bit from the surface to 207'. Reduced the hole to 9 7/8" at 207'. Cleaned a 9 7/8" hole from 207' to the top of the existing 8 5/8" casing at 1009'. Reduced the hole to 7 7/8" at 1009'. Cleaned 7 7/8" hole from 1009' to 1256'. Attempted to remove 8 5/8" casing by pulling 150% of the string weight but all attempts to remove the existing 8 5/8" casing were unsuccessful. Left an unknown amount of 8 5/8" casing in the hole from 1009' to unknown depth. Cut remaining 8 5/8" casing at 1201', 1151', 1101' and 1051'. The 8 5/8" casing was previously ripped from 1109' to 1014' and from 1174' to 1223'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (993.8' -1001.1'). Left 20' of 16" conductor pipe in hole from surface to 20'. Cemented the hole from 1256' to surface as follows: From 1256' to 793' with 190 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. From 793' to surface with 430 sacks of Expandable Cement. Cement did circulate at surface. A total of 620 sacks of cement were used to fill the hole from 1256' to surface.	8 5/8" Casing 16" Conductor	0 0	Unknown 20'	
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>993.8' – 1001.1'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 15th day of April, 2021


And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright



Sworn to and subscribed before me this 11th day of May, 2021

[Signature]
Notary Public

06/11/2021

My commission expires: 09/15/22

Permit No. 47-103-03328
Well No. 4527
Latitude: 39° 38' 45.06"N
Longitude: -80° 24' 39.69"W