

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Lloyd F. Cain Operator Well No.: 7180

LOCATION: Elevation: 1075.77 Quadrangle: Folsom, WV 7.5'  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 29 Min. 28.46 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 31 Min. 20.85 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company Consolidation Coal Co. Coal Operator Consolidation Coal Co.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554

Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 10/18/2019 or Owner \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 10th day of May, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thickotropic w/ Green Dye and Gas Block	1120'	753'		
Expandable Cement	753'	Surface		
7" Casing	816'	Unknown	0'	Unknown
16" Conductor	Surface	18'	0'	18'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 1st day of June, 2021.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 21st day of June, 2021  
My commission expires: 09/15/22  
[Signature]  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector 6/22/21

08/13/2021

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
EVERETT & EDITH HAUGHT  
Lease or Property Owner  
28569 SHORTLINE HWY FOLSOM, WV 26348  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
FOLSOM WV 7.5'  
Well Location  
GRANT  
District  
WETZEL  
County  
7180  
Well No.  
LLOYD F. CAIN  
Farm


STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris 6/22/21  
AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Co. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 10<sup>th</sup> day of May, 2020 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned the hole with a 12 1/4" bit from the surface to 375'. Reduced the hole to 9 7/8" at 375'. Cleaned the hole with a 9 7/8" bit from 375' to 721'. Reduced the hole to 7 7/8" at 721'. Cleaned the hole with a 7 7/8" bit from 721' to 816'. Tagged top of 7" casing at 816'. Reduced hole to 6 1/4" at 816'. Cleaned a 6 1/4" hole through 7" casing from 816' to 1120'. Attempted to remove the 7" casing by pulling 150% of the string weight. All attempts to remove the 7" casing were unsuccessful. Left an unknown amount of 7" casing in the hole from 816' to unknown depth. The remaining 7" casing was cut at 1118', 1068', 1018', 968', 928', 923', 918', 916', 913.50', 911', 906', 901', and 861'. Left 7" casing through the Pittsburgh Coal Seam (910.9' - 917.8'). Left 18' of 16" conductor pipe in the hole from the surface to 18'.		7" Casing  16" Conductor	0'  0'	Unknown  18'
<b>Cemented the hole from 1120' to surface as follows:</b> From 1120' to 763' with 115 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. Tagged top of Thixotropic plug at 763'. From 763' to surface with 545 sacks of Expandable Cement. Cement did circulate at surface. A total of 660 sacks of cement were used to fill the hole from 1120' to surface.				
<b>Coal Seams</b>	<b>Description of Monument</b>			
<u>Pittsburgh</u>	<u>910.9' – 917.8'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 1<sup>st</sup> day of June, 2021

And further deponents saith not.



Matthew A. Yearsley  
Matthew A. Yearsley

Kevin S. Wright  
Kevin S. Wright

Sworn to and subscribed before me this 21<sup>st</sup> day of June, 2021

08/13/2021

[Signature]  
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03333  
Well No. 7180  
Latitude: 39° 29' 28.46"N  
Longitude: -80° 31' 20.85"W