

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B.W. Peterson Operator Well No.: 7383

LOCATION: Elevation: 1214.32 Quadrangle: Folsom W.VA  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 29 Min. 36.2904 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 32 Min. 12.7392 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company Consolidation Coal Co. Coal Operator Consolidation Coal Co.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Coal Operator \_\_\_\_\_  
Agent David Roddy or Owner \_\_\_\_\_  
Permit Issued Date 08/26/2020

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 6th day of November, 2020, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable Cement w/ Gas Blocker	2283'	1244'		
Thixotropic Cement w/ Green Dye	1244'	823'		
Expandable Cement	823'	Surface		
7" Casing	1244'	2233'	1214'	1001'
16" Conductor Pipe	Surface	18'	0'	18'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 9th day of Decemeber, 2020.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 11<sup>th</sup> day of Jan, 2021

My commission expires: 09.15.22  
[Signature]  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Derek M. Haught Title: Oil & Gas Inspector 03/26/2021

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
COASTAL FOREST RESOURCES COMPANY  
Lease or Property Owner  
P.O. BOX 709 BUCKHANNON, WV 26201  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
FOLSOM W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
7383  
Well No.  
B.W. PETERSON  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Derek M. Haught

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 6<sup>th</sup> day of November, 2020 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned out existing 7" casing with a 6 1/4" bit from 18' to 2283'. Tagged a plug at 2283'. Set bottom hole cement plug from 2283' back to 1244' with 175 sacks of Expandable Cement with a gas blocker additive. Removed 1214' of 7" casing from 18' to 1232'. Left 1001' of 7" casing in the hole from 1232' to 2233'. Cleaned the hole with a 12 1/4" bit from the surface to 454'. Reduced the hole to 9 7/8" at 454'. Cleaned the hole with a 9 7/8" bit from 454' to the top of the remaining 7" casing at 1232'. Reduced the hole to 6 1/4" at 1232'. Cleaned the hole with a 6 1/4" bit from 1232' to the top of the bottom hole plug at 1244'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1023.4' - 1029.9'). Left 18' of 16" conductor pipe in the hole from the surface to 18'.		7" Casing 16" Conductor	1214' 0'	1001' 18'
<b>Cemented the hole from 1244' to surface as follows:</b> From 1244' to 823' with 220 sacks of Thixotropic Cement with Green Dye. From 823' to surface with 450 sacks of Expandable Cement. Cement did circulate at surface. A total of 670 sacks of cement were used to cement the hole from 1244' to surface.				
<b>Coal Seams</b>	<b>Description of Monument</b>			
<u>Pittsburgh</u>	1023.4' - 1029.9'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 9<sup>th</sup> day of December, 2020

And further deponents saith not.



Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

Sworn to and subscribed before me this 11<sup>th</sup> day of Jan 2021

Derek M. Haught 03/26/2021  
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03361  
Well No. 7383  
Latitude: 39° 29' 36.2904"N  
Longitude: -80° 32' 12.7392"W