

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B.W. Peterson Operator Well No.: 7274B

LOCATION: Elevation: 1086.41' Quadrangle: Folsom, WV  
District: Grant County: Wetzel  
Latitude: 39.499285 Feet South of 39 Deg. 29 Min. 57.42 Sec.  
Longitude: -80.525021 Feet West of -80 Deg. 31 Min. 30.07 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company Consolidation Coal Co. Coal Operator Consolidation Coal Co.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
or Owner \_\_\_\_\_  
Permit Issued Date 11/02/2020

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 2nd day of November, 2020, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1118'	701'		
Expandable Cement	701'	Surface		
16" Conductor Pipe	Surface	29'	0'	29'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 13th day of November, 2020.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 19th day of NOV, 2020

My commission expires: 09/15/20  
Thomas J. Sullivan  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Derek M. Haught Title: Oil & Gas Inspector

03/12/2021

# Plugging Report for MSHA

Well Number: 7274B

Mine: Harrison County Mine

Surface

Permit Number: 47-103-03364

Date Clean Out Started: 11/2/2020

Date Well Bore Plugged: 11/13/2020

Pittsburgh Coal Seam: 901 ft. To 907 ft.

Plugs:	From	To	Type of Cement
	<u>1118'</u>	<u>701'</u>	<u>Thixotropic Cement w/ Green Dye and Gas Block</u>
	<u>701'</u>	<u>Surface</u>	<u>Expandable Cement</u>

**Casing Remaining in Well Bore**

Thix Top: 701'

	Top	Bottom	Left	Pulled
Sucker Rods				
2 3/8" tubing				
4 1/2" casing				
7" casing				
7" fiberglass				
8 5/8" casing				
10 3/4" casing				
16" Conductor	Surface	29'	29'	0'

Expandable Cement

Top of 16" Conductor at Surface

Bottom of 16" Conductor at 29'

Thixotropic Cement w/ Green Dye

901' - 907'

Pittsburgh Coal

**Cement:**

Expandable	<u>380</u>	sacks
Thixotropic	<u>195</u>	sacks
Econofill		sacks
Mud Flush	<u>1000</u>	gal
Other		
Est. Top Thix		ft
Did Cement Circ.	<u>Yes</u>	

**Comments:**

Caving: Extreme Moderate **Normal**

Lost Circulation: Extreme **Moderate** Normal

Difficulty in Removing Casing: Extreme Moderate Normal **Does Not Apply**

Debris in Well Bore: **Wood** Steel Other: \_\_\_\_\_

Thixotropic Cement w/ Green Dye

Surface Elevation (Surveyed)	<u>1086'</u>
Bottom of Coal Structure (Map)	<u>179'</u>
Difference	<u>907'</u>

Thix Bottom: 1118'

Total Depth: 1118'

03/12/2021

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

COASTAL FOREST RESOURCES COMPANY  
Lease or Property Owner  
P.O. BOX 709 BUCKHANNON, WV 26201  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address

FOLSOM, WV  
Well Location  
GRANT  
District  
WETZEL  
County  
7274B  
Well No.  
B.W. PETERSON  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Derek M. Haught

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 2<sup>nd</sup> day of November, 2020 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned a 12 1/4" hole from the surface to 331'. Reduced hole to 9 7/8" at 331'. Cleaned a 9 7/8" hole from 331' to 1118'. Tagged plug at 1118'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (901' - 907'). Left 29' of 16" conductor pipe in the hole from the surface to 29'.  <b>Cemented the hole from 1118' to surface as follows:</b> From 1118' to 701' with 195 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. Tagged the cement plug at 701'. From 701' to surface with 380 sacks of Expandable Cement. Cement did circulate at surface. A total of 575 sacks of cement were used to fill the hole from 1118' to surface.	16" Conductor	0'	29'	
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	901' - 907'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 13<sup>th</sup> day of November, 2020

And further deponents saith not.



Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

Sworn to and subscribed before me this 19<sup>th</sup> day of Nov, 2020

[Signature] 03/12/2021  
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03364  
Well No. 7274B  
Latitude: 39° 29' 57.42"N  
Longitude: -80° 31' 30.07"W