

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B.W. Peterson Operator Well No.: 7202A

LOCATION: Elevation: 1450' Quadrangle: Folsom, WV  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 29 Min. 50.36 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 31 Min. 55.79 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company West Virginia Land Resources Inc. Coal Operator West Virginia Land Resources Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah WV 26554 Monongah WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
or Owner \_\_\_\_\_  
Permit Issued Date 03/29/2021

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 17th day of June, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1473'	1067'		
Expandable Cement	1067'	Surface		
8 5/8" Casing	1,478	Unknown	688'	Unknown
16" Conductor Casing	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 7th day of July, 2021.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 20th day of July, 2021

My commission expires: 09/15/22  
[Signature]  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Ham Title: Inspector **08/13/2021**

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
COASTAL FOREST RESOURCES  
Lease or Property Owner  
PO BOX 709 BUCKHANNON, WV 26201  
Address

WEST VIRGINIA LAND RESOURCES INC.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
FOLSOM WV  
Well Location  
GRANT  
District  
WETZEL  
County  
7202A  
Well No.  
B.W. PETERSON  
Farm


STATE INSPECTOR SUPERVISING PLUGGING *Bryan Harris*  
AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 17<sup>TH</sup> day of June, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
	Cleaned the hole with a 12 1/4" bit from the surface to 418'. Reduced the hole to 9 7/8" at 418'. Cleaned the hole with a 9 7/8" bit from 418' to 790'. Tagged 8 5/8" casing at 790'. Reduced the hole to 7 7/8" at 790'. Cleaned the hole with a 7 7/8" bit from 790' to 1500'. Removed 688' of 8 5/8" casing from 790' to 1478'. Attempted to remove remaining 8 5/8" casing by pulling 150% of the string weight but all attempts were unsuccessful. Left unknown amount of 8 5/8' casing in the hole from 1478' to unknown depth. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam from 1267' to 1273'. Left 20' of 16" conductor in the hole from the surface to 20'.	8 5/8" Casing 16" Conductor	688' 0'	Unknown 20'
<b>Cemented the hole from 1067' to the surface as follows:</b>				
From 1478' to 1067 with 250 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. Tagged top of Thixotropic at 1067'. Cemented the hole from 1067 to the surface with 615 sacks of Expandable Cement. Cement did circulate at surface. A total of 865 sacks of cement were used to fill the hole from 1478' to the surface.				
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	1,267' – 1,273'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 7<sup>th</sup> day of July, 2021

And further deponents saith not.



*Matthew A. Yearsley*  
Matthew A. Yearsley

*Kevin S. Wright*  
Kevin S. Wright

Sworn to and subscribed before me this 20<sup>th</sup> day of July, 2021

*[Signature]* 08/13/2021  
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03377  
Well No. 7202A  
Latitude: 39° 29' 50.37"N  
Longitude: -80° 31' 55.79"W