

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: O.P. McIntyre Operator Well No.: 7362

LOCATION: Elevation: 1164' Quadrangle: Folsom, W.VA  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 29 Min. 18.49 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 30 Min. 07.98 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company West Virginia Land Resources Inc Coal Operator West Virginia Land Resources, Inc  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 03/29/2021 or Owner \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 26th day of August, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1277'	862'		
Expandable Cement	862'	Surface		
2 3/8" Tubing	Surface	1,080'	1,080'	0'
7" Casing	910'	Unknown	367'	Unknown
8 5/8" Casing	910'	Unknown	367'	Unknown
16" Conductor Casing	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 16th day of November, 2021.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 30th day of Nov, 20 21  
My commission expires: 09/15/22  
[Signature]  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

WEST VIRGINIA LAND RESOURCES INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

COASTAL FOREST RESOURCES CO.  
Lease or Property Owner  
P.O. BOX 709 BUCKHANNON, WV 26201  
Address

WEST VIRGINIA LAND RESOURCES INC.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address

FOLSOM W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
7362  
Well No.  
O.P. MCINTYRE  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris Inspector  
AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 26<sup>th</sup> day of August, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Removed all 2 3/8" tubing from the surface to 1080'. Cleaned a 12 1/4" hole from the surface to 417'. Reduced the hole to 9 7/8" at 417'. Cleaned a 9 7/8" hole from 417' to the top of the existing 7" and 8 5/8" casing at 910'. Reduced the hole to 6 1/4" at 910'. Cleaned a 6 1/4" hole from 910' to 1277'. Removed 367' of 7" casing from 910' to 1277'. Left an unknown amount of 7" casing in the hole from 1277' to unknown depth. Removed 367' of 8 5/8" casing from 910' to 1277'. Left an unknown amount of 8 5/8" casing in hole from 1277' to an unknown depth. Cleaned a 9 7/8" hole from 910' to 1277'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1062.7' to 1069.9'). Left 20' of 16" Conductor in hole from the surface to 20'.		2 3/8"	1,080'	0'
		7" Casing	367'	Unknown
		8 5/8" Casing	367'	Unknown
		16" Conductor	0'	20'
<b>Cemented the hole from 1277' to the surface as follows:</b> From 1277' to 862' with 200 sacks of Thixotropic Cement with Green Dye and gas blocker additive. From 862' to the surface with 435 sacks of Expandable Cement. Cement did circulate at the surface. A total of 635 sacks of cement were used to fill the hole from 1277' to the surface.				
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	<u>1062.7' - 1069.9'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 16<sup>th</sup> day of November, 2021

And further deponents saith not.



Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

Sworn to and subscribed before me this 30<sup>th</sup> day of Nov, 2021

[Signature] 04/08/2022  
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03378  
Well No. 7362  
Latitude: 39° 29' 18.49"N  
Longitude: -80° 30' 07.98"W