

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B. W. Peterson Operator Well No.: 7234

LOCATION: Elevation: 1268.25' Quadrangle: Big Run, WV 7.5'  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 30 Min. 06.09 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 32 Min. 19.61 Sec.

Well Type: OIL  GAS \_\_\_\_\_

Company West Virginia Land Resources, Inc. Coal Operator Consolidation Coal Co  
46226 National Road or Owner 1 Bridge Street  
St. Clairsville, OH 43950 Monongah, WV 26554  
Coal Operator \_\_\_\_\_  
Agent David Roddy or Owner \_\_\_\_\_  
Permit Issued Date 05/13/2021

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 3rd day of June, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thirotropic w/ Green Dye and Gas Block	1,440'	945'		
Expanding Cement	945'	Surface		
8 5/8" Casing	1086'	Unknown	184'	Unknown
16" Conductor	Surface	20'	0'	Unknown

Description of monument: .77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 18th day of June, 2021.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 29th day of June, 2021

My commission expires: 09/15/22 [Signature]  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector 08/13/2021

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
MAGNOLIA LAND PARTNERS LLC  
Lease or Property Owner  
601 WALNUT ST, PHILADELPHIA, PA 19106  
Address

WEST VIRGINIA LAND RESOURCES INC.  
Name of Well Operator  
46226 NATIONAL ROAD  
Complete Address  
ST. CLAIRSVILLE, OH 43950  
Well Location  
GRANT  
District  
WETZEL  
County  
7234  
Well No.  
B. W. PETERSON  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris 7/6/21  
AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 3rd day of June, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleansed hole with 12 1/4" bit from the surface to 398'. Reduced the hole to 9 7/8" at 398'. Cleaned the hole with a 9 7/8" bit from 398' to the top of the existing 8 5/8" casing at 902'. Reduced the hole to 6 1/4" at 902'. Cleaned the hole with a 6 1/4" bit from 902' to 1440'. Removed 184' of 8 5/8" casing from 902' to 1086'. Attempted to pull remaining 8 5/8" casing by pulling 150% of the string weight but all attempts were unsuccessful. Left an unknown amount of 8 5/8" casing on the hole from 1086' to and unknown depth. Cut remaining 8 5/8" casing at the following depths: 1303', 1252', 1202', 1152', 1112', 1107', 1102', 1100', 1098', 1096'. 8 5/8" casing was previously cut at 1091'. Cleaned a 7 7/8" hole through the Pittsburgh Coal Seam (1096' - 1102'). Left 20' of 16" conductor pipe in hole from the surface to 20'.		8 5/8" Casing	184'	Unknown
		16" Conductor	0'	20'
<b>Cemented the hole from 1440' to surface as follows.</b> From 1440' to 945' with 215 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. Tagged top of Thixotropic Cement plug at 945'. Cemented the hole from 945' to surface with 580 sacks Expandable Cement. Cement did circulate at the surface. A total of 795 sacks of cement were used to fill the hole from 1440' to surface.				
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	1096' - 1102'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 18<sup>th</sup> day of June, 2021

And further deponents saith not.

Matthew A. Yearsley  
Matthew A. Yearsley  
Kevin S. Wright  
Kevin S. Wright



Sworn to and subscribed before me this 29<sup>th</sup> day of June, 2021

[Signature] 08/13/2021  
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03388  
Well No. 7234  
Latitude: 39° 30' 06.09" N  
Longitude: 80° 32' 19.61" W