

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Genine Robinson Operator Well No.: 6730

LOCATION: Elevation: 1512' Quadrangle: Folsom WV  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 29 Min. 12.27 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 30 Min. 20.21 Sec.

Well Type: OIL  GAS \_\_\_\_\_

Company West Virginia Land Resources Inc Coal Operator West Virginia Land Resources Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Coal Operator \_\_\_\_\_  
Agent David Roddy or Owner \_\_\_\_\_  
Permit Issued Date 04/29/2021

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 26th day of May, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thiotropic w/ Green Dye and Gas Block	1658'	1202'		
Expandable Cement	1202'	Surface		
2 3/8" Tubing	112'	1,335'	1,335'	0'
8 5/8" Casing	413'	Unknown	0' (multiple cuts, rips and partings)	Unknown
16" Conductor Casing	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 9th day of July, 2021.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 2nd day of Aug, 2021

My commission expires: 09/15/22  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector

09/20/2024

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
ROBERT P. & RANDALL B. NICHOLS  
Lease or Property Owner  
6753 N RIDGE ROAD MADISON, OH 44057  
Address

WEST VIRGINIA LAND RESOURCES INC.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
FOLSOM WV  
Well Location  
GRANT  
District  
WETZEL  
County  
6730  
Well No.  
ROBERT P. & RANDALL B. NICHOLS  
Farm


STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris 8/4/21  
AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 26<sup>TH</sup> day of May, 2021 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned 12 1/4" hole from the surface to 112'. Tagged top of 2 3/8" tubing at 112'. Removed 2 3/8" tubing from 112' to 1,447'. Continued to clean a 12 1/4" hole from 112' to 126'. Reduced the hole to 9 7/8" at 126'. Cleaned a 9 7/8" hole from 126' to 413'. Tagged 8 5/8" casing at 413'. Cleaned out 8 5/8" casing with a 7 7/8" bit from 413' to 1,658'. Attempted to remove 8 5/8" casing by pulling 150% of string weight. All attempts to remove 8 5/8" casing were unsuccessful. Cut 8 5/8" casing at 1,609', 1,559', 1,509', 1,459', 1,419', 1,414', 1,409', 1,407', 1,404.5, 1,402', 1,397', 1,392', 1,352', and 1,302'. The 8 5/8" casing was previously ripped or parted as follows: ripped 1427' to 1386', parted 1386' to 1380', ripped 1380' to 1376', ripped 1244' to 1236', parted 1172' to 1169', parted 1047' to 1045', ripped 863' to 857', ripped 741' to 737', ripped 732' to 722', ripped 708' to 669', ripped 597' to 589', ripped 534' to 527'. Left unknown amount of 8 5/8" casing in hole from 413' to an unknown depth. Cleaned a 7 7/8" hole through thee Pittsburgh Coal Seam (1,402' - 1,409'). Left 20' of 16" conductor in the hole from 20' to surface. <b>Cemented the hole from 1,658' back to the surface as follows:</b> From 1658' back to 1202' with 150 sacks Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged Thixotropic plug at 1202'. Cemented the hole from 1202' back to surface with 340 sacks of Expandable Cement. Cement did circulate at surface.	2 3/8" Tubing	1335'	0'	
		8 5/8" Casing	0'	Unknown
		16" Conductor	0'	20'
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	1402' - 1409'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 9<sup>th</sup> day of July, 2021

And further deponents saith not.



Sworn to and subscribed before me this 24<sup>th</sup> day of Aug, 2021

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

[Signature]

Notary Public

09/20/2024

My commission expires: 09/15/22

Permit No. 47-103-03389  
Well No. 6730  
Latitude: 39° 29' 12.27"N  
Longitude: -80° 30' 20.21"W