

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Samuel Barker Operator Well No.: 7281

LOCATION: Elevation: 1348' Quadrangle: Big Run W.VA
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 30 Min. 13.17 Sec.
Longitude: _____ Feet West of -80 Deg. 30 Min. 57.28 Sec.

Well Type: OIL X GAS _____

Company West Virginia Land Resources Inc Coal Operator West Virginia Land Resources Inc
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Coal Operator _____
Agent David Roddy or Owner _____
Permit Issued Date 04/21/2021

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 8th day of July, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1410'	1010'		
Expandable Cement	1010'	Surface		
8 5/8" Casing	1095'	Unknown	0' (Multiple Cuts)	Unknown
10 3/4" Casing	604'	743'	0'	139'
16" Conductor	Surface	26'	0'	26'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 26th day of July, 2021.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 19th day of Aug, 2021
My commission expires: 09/15/22
[Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector 01/19/2024

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
JOHN W SHRIVER ET AL (C/O RENEE EVANS)
Lease or Property Owner
704 GREENWOOD MANOR CIR MELBOURNE, FL 32904
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
BIG RUN W.VA
Well Location
GRANT
District
WETZEL
County
7281
Well No.
SAMUEL BARKER
Farm

STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris 8/23/21

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 8th day of July, 2021 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
	Cleaned a 12 1/4" hole from the surface to 215'. Reduced the hole to 9 7/8" hole at 215'. Cleaned a 9 7/8" hole from 215' to 1095'. Tagged top of existing 8 5/8" casing at 1095'. Reduced the hole to 7 7/8" at 1095'. Cleaned a 7 7/8" hole through the 8 5/8" casing from 1095' to 1410'. Attempted to remove the existing 8 5/8" casing by pulling 150% of string weight but all attempts were unsuccessful. Left unknown amount of 8 5/8" casing in the hole from 1095' to an unknown depth. Cut remaining 8 5/8" casing at 1390', 1329', 1279', 1220', 1189', 1184', 1179', 1177', 1175', 1173', 1168', 1163' and 1123'. Cleaned a 7 7/8" hole through the Pittsburgh Coal Seam (1173' - 1179.1'). Left 139' of 10 3/4" casing from 604' to 743'. Left 26' of 16" conductor in the hole from the surface to 26'.	8 5/8" Casing 10 3/4" Casing 16" Conductor	0' 0' 0'	Unknown 139' 26'
	<u>Cemented the hole from 1410' to surface as follows:</u> From 1410' to 1010' with 160 sacks of Thixotropic Cement w/ Green Dye and a Gas Blocker additive. From 1010' to surface with 590 sacks of Expandable Cement. Cement did circulate at the surface.			
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	1173' - 1179.1'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 26th day of July, 2021

And further deponents saith not.



Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

Sworn to and subscribed before me this 19th day of Aug, 2021

01/19/2024

[Signature]

Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03393
Well No. 7281
Latitude: 39° 30' 13.17"N
Longitude: -80° 30' 57.22"W