

**STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS**

**AFFIDAVIT OF PLUGGING AND FILLING WELL**

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: I. D. Morgan Operator Well No.: 7259

LOCATION: Elevation: 919.36' Quadrangle: Big Run, W.VA  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 30 Min. 21.22 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 32 Min. 12.07 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company	<u>West Virginia Land Resources, Inc.</u>	Coal Operator	<u>West Virginia Land Resources, Inc</u>
	<u>1 Bridge Street</u>	or Owner	<u>1 Bridge Street</u>
	<u>Monongah, WV 26554</u>		<u>Monongah, WV 26554</u>
Agent	<u>David Roddy</u>	Coal Operator	_____
Permit Issued Date	<u>05/06/2021</u>	or Owner	_____

**AFFIDAVIT**


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 7th day of November, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable Cement w/ Gas Blocker	2060'	992'		
Thixotropic Cement	992'	511'		
Expandable Cement	511'	Surface		
5 1/2" Casing			1950'	0'
7" Casing	727.5'	1972'	727.5'	1244.5'
16" Conductor	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 17th day of November, 2021.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 12th day of Jan, 2022

My commission expires: 09/15/22 [Signature]  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector 04/15/2022

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

WEST VIRGINIA LAND RESOURCES INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

SOUTHERN COUNTRY FARMS INC.  
Lease or Property Owner  
P.O. BOX 40 SINKS GROVE, WV 24976  
Address

WEST VIRGINIA LAND RESOURCES INC.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address

BIG RUN, W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
7259  
Well No.  
I. D. MORGAN  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris Inspector  
AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 7<sup>th</sup> day of November, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Removed all 5 1/2" casing from the surface to 1950'. Cleaned out existing 7" casing with a 6 1/4" bit from the surface to 2060'. Cemented the bottom hole from 2060' to 992' with 175 sacks of Expandable Cement with a Gas Blocker additive. Removed 705' of 7" casing from the surface to 705'. Pilot milled 7" casing from 705' to 727.5'. Attempted to pull remaining 7" casing by pulling 150% of the string weight but all attempts were unsuccessful. Left 1244.5' of 7" casing in the hole from 727.5' to 1972'. Cut remaining 7" casing at 917.5', 867.5', 817.5', and 767.5'. Cleaned a 9 7/8" hole from the surface to 727.5'. Tagged the top of the remaining 7" casing at 727.5'. Cleaned the hole with a 6 1/4" bit from 727.5' to the top of the bottom hole plug at 992'. Cleaned 9 7/8" hole through the Pittsburgh Coal Seam (711.1' to 717.5'). Left 20' of 16" Conductor in the hole from the surface to 20'.		5 1/2" Casing	1950'	0'
		7" Casing	727.5'	1244.5'
		16" Conductor	0'	20'
<b><u>Cemented the hole from 992' back to the surface as follows:</u></b> From 992' to 511' with 190 sacks of Thixotropic Cement with Green Dye. From 511' to surface with 355 sacks of Expandable Cement. Cement did circulate at the surface. A total of 720 sacks of cement were used to fill the hole from 2060' to the surface.				
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	711.1' – 717.5'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 17<sup>th</sup> day of November, 2021

And further deponents saith not.



Sworn to and subscribed before me this 12<sup>th</sup> day of Jan, 2022

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

04/15/2022

[Signature]  
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03401  
Well No. 7259  
Latitude: 39° 30' 21.22"N  
Longitude: -80° 32' 12.07"W