

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: I. D. Morgan Operator Well No.: 7237

LOCATION: Elevation: 1122.07' Quadrangle: Big Run, WV
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 30 Min. 10.11 Sec.
Longitude: _____ Feet West of -80 Deg. 32 Min. 10.13 Sec.

Well Type: OIL X GAS _____

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monogah, WV 26554 Monogah, WV 26554
Coal Operator _____
Agent David Roddy or Owner _____
Permit Issued Date 06/24/2021

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monogalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 28th day of September, 2021, and the well was plugged and filled in the following manner:

| TYPE | FROM | TO | PIPE REMOVED | LEFT |
|--|---------|---------|--------------|------|
| Thixotropic w/ Green Dye and Gas Block | 1130' | 699' | | |
| Expandable Cement | 699' | Surface | | |
| 16" Conductor Casing | Surface | 100' | 0' | 100' |
| | | | | |
| | | | | |

Description of monument: 77" of 7" casing with company name, well #, API#, and date cemented and that the work of plugging and filling said well was completed on the 26th day of October, 2021.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 1st day of Nov, 2021

My commission expires: 09/15/22

[Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector 03/18/2022

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
SOUTHERN COUNTRY FARMS INC
Lease or Property Owner
P.O. BOX 40 SINKS GROVE, WV 24976
Address

WEST VIRGINIA LAND RESOURCES INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
BIG RUN, WV
Well Location
GRANT
District
WETZEL
County
7237
Well No.
I.D. MORGAN
Farm

STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris Inspector

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 28th day of September, 2021 and that the well was plugged in the following manner:


| Sand or Zone Record Formation | Filling Material | Casing/Tubing Size | Casing Pulled | Casing Left In |
|-------------------------------|--|--|---------------|----------------|
| | Cleaned the hole with a 12 1/4" bit from the surface to 350'. Reduced the hole to 9 7/8" at 350'. Cleaned the hole with a 9 7/8" bit from 350' to 1130'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (899.4' - 905.9') Left 100' of 16" conductor in the hole from the surface to 100'. Cemented the hole from 1130' to the surface as follows: From 1130' to 699' with 270 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. Tagged top of Thixotropic plug at 699'. Cemented the hole from 699' to the surface with 435 sacks of Expandable Cement. Cement did circulate at the surface. A total of 705 sacks of cement were used to fill the hole from 1130' to the surface. | 16" Conductor Casing | 0' | 100' |
| Coal Seams | | Description of Monument | | |
| <u>Pittsburgh</u> | 899.4' - 905.9' | 77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level. | | |

... and that the work of plugging and filling said well was completed on the 26th day of October, 2021

And further deponents saith not.

Matthew A. Yearsley
Matthew A. Yearsley

Kevin S. Wright
Kevin S. Wright



Sworn to and subscribed before me this 13th day of Nov, 2021

[Signature]
Notary Public 03/18/2022

My commission expires: 09/15/22

Permit No. 47-103-03419
Well No. 7237
Latitude: 39° 30' 10.11"N
Longitude: -80° 32' 10.13"W