

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: M.J. Morris Operator Well No.: 7361

LOCATION: Elevation: 1029.83' Quadrangle: Wallace WV
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 29 Min. 31.19 Sec.
Longitude: _____ Feet West of -80 Deg. 29 Min. 57.97 Sec.

Well Type: OIL X GAS _____

Company West Virginia Land Resources Inc Coal Operator West Virginia Land Resources Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Coal Operator _____
Agent David Roddy or Owner _____
Permit Issued Date 09/30/2021 _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 1st day of November, 2021, and the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1168'	741'		
Expandable Cement	741'	Surface		
7" Casing	1168'	Unknown	312'	Unknown
8 5/8" Casing	992'	Unknown	0' (multiple cuts installed)	Unknown
16" Conductor	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 7th day of December, 2021.

And further deponents saith not. Matthew A. Yearsley

Kevin S. Wright

Sworn and subscribe before me this 6th day of Jan, 2022



My commission expires: 09/15/22

[Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector

04/15/2022

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
ROBERT P & RANDALL B NICHOLS
Lease or Property Owner
6753 N RIDGE ROAD, MADISON, OH 44057
Address

WEST VIRGINIA LAND RESOURCES INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
WALLACE, WV
Well Location
GRANT
District
WETZEL
County
7361
Well No.
M.J. NORRIS
Farm


STATE INSPECTOR SUPERVISING PLUGGING Bryan Harris Inspector
AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 1st day of November, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned a 12 1/4" hole from the surface to 329'. Reduced the hole to 9 7/8" at 329'. Cleaned a 9 7/8" hole for 329' to the top of the existing 7" casing at 856'. Reduced hole to 6 1/4" at 856'. Cleaned a 6 1/4" hole from 856' to 1168'. Removed 312' of 7" casing from 856' to 1168'. Left an unknown amount of 7" casing in the hole from 1168' to an unknown depth. Cleaned a 9 7/8" hole from 856' to the top of the existing 8 5/8" casing at 992'. Attempted to pull the 8 5/8" casing from 992' by pulling 150% of the string weight but all attempts were unsuccessful. Left an unknown amount of 8 5/8" casing in the hole from 992' to an unknown depth. Cut remaining 8 5/8" casing 1148', 1098' and 1048'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (941' - 948'). Left 20' of 16" conductor in the hole from the surface to 20'.		7" Casing	312'	Unknown
		8 5/8" Casing	0'	167'
		16" Conductor	0'	20'
<u>Cemented the hole from 1168' back to the surface as follows:</u> From 1168' to 741' with 170 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. Tagged top of Thixotropic Cement plug at 741'. Cemented the hole from 741' to the surface with 375 sacks of Expandable Cement. Cement did circulate at the surface. A total of 544 sacks of cement were used to fill the hole from 1168' to the surface.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>941' - 948'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 7th day of December, 2021

And further deponents saith not.



Sworn to and subscribed before me this 6th day of Jan, 2022

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

04/15/2022

[Signature]
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03455
Well No. 7361
Latitude: 39° 29' 31.19"N
Longitude: -80° 29' 57.97"W