

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Brame Higgins Operator Well No.: 6343

LOCATION: Elevation: 1031.10' Quadrangle: Wallace, W.VA  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 29 Min. 34.01 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 29 Min. 48.45 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Coal Operator \_\_\_\_\_  
Agent David Roddy or Owner \_\_\_\_\_  
Permit Issued Date 11/2/2021

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 18th day of November, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1144'	732'		
Expandable Cement	732'	Surface		
8 5/8" Casing	769'	1137'	409' (multiple cuts and perforations installed)	368'
13 3/8" Conductor	Surface	38'	0'	38'

Description of monument: 77" of 7" casing with company name, well #, API#, and date cemented and that the work of plugging and filling said well was completed on the 9th day of December, 2021.


And further deponents saith not. Matthew A. Yearsley

Kevin S. Wright

Sworn and subscribe before me this 6<sup>th</sup> day of Jan, 2022

My commission expires: 09/15/22

[Signature]  
Notary Public



Affidavit reviewed by the Office of Oil and Gas: Bryan Harris Title: Inspector

04/15/2022

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

WEST VIRGINIA LAND RESOURCES, INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
ROBERT P. & RANDALL B. NICHOLS  
Lease or Property Owner  
6753 N RIDGE ROAD, MADISON, OH 44057  
Address

WEST VIRGINIA LAND RESOURCES, INC.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
WALLACE, WV  
Well Location  
GRANT  
District  
WETZEL  
County  
6343  
Well No.  
BROME HIGGINS  
Farm

STATE INSPECTOR SUPERVISING PLUGGING \_\_\_\_\_

*Bryan Harris*

Inspector

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 18<sup>th</sup> day of November, 2021 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned a 9 7/8" hole from the surface to top of the existing 8 5/8" casing at 362'. Reduced hole to 7 7/8" at 362'. Cleaned a 7 7/8" hole through the 8 5/8" casing from 362' to 1144'. Removed 409' of 8 5/8" casing from 362' to 769'. Made several attempts to remove remaining 8 5/8" casing from 769' by pulling 150% of string weight. All attempts to remove the remaining 8 5/8" casing were unsuccessful. Left 368' of 8 5/8" casing in hole from 769' to 1137'. Cut remaining 8 5/8" casing at 1091', 1041', 991', 951', 946', 941', 939.5', 938', 882', and 832'. Perforated 8 5/8" casing with 6 shots at each of the following depths, 936.5', 935', 933.5', 932', 927', 922'. Cleaned a 7 7/8" through the Pittsburgh Coal Seam (932.7' to 939.9'). Left 38' of 13 3/8" conductor in hole from the surface to 38'.		8 5/8" Casing	409'	368'
		13 3/8" Conductor	0'	38'
<b>Cemented the hole from 1144' back to surface as follows:</b> From 1144' to 732' with 130 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. From 732' back to the surface with 300 sacks of Expandable Cement. Cement did circulate at the surface. A total of 430 sacks of cement were used to fill the hole from 1144' to the surface.				
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	<u>932.7' - 939.9'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 9<sup>th</sup> day of December, 2021


And further deponents saith not.

*Matthew A. Yearsley*

Matthew A. Yearsley

*Kevin S. Wright*

Kevin S. Wright



Sworn to and subscribed before me this 6<sup>th</sup> day of Jan, 2022

*[Signature]*

Notary Public

04/15/2022

My commission expires: 09/15/22

Permit No. 47-103-03465  
Well No. 6343  
Latitude: 39° 29' 34.01"N  
Longitude: -80° 29' 48.45"W