

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: W.G. Snodgrass Operator Well No.: 8274

LOCATION: Elevation: 1188.72' Quadrangle: Hundred W.VA, PA  
District: Church County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 39 Min. 35.83 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 24 Min. 52.72 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
or Owner \_\_\_\_\_  
Permit Issued Date 02/16/2022

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 11th day of March, 2022, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1243'	809'		
Expandable Cement	809'	Surface		
16" Conductor	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 23rd day of March, 2022.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 29th day of Mar, 20 22  
My commission expires: 09/15/22  
[Signature]  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: \_\_\_\_\_ Title: \_\_\_\_\_



AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

BETTY E. STEWART  
Lease or Property Owner  
13023 MASON DIXON HWY. BURTON, WV 26562  
Address

WEST VIRGINIA LAND RESOURCES, INC.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
HUNDRED W.VA, PA  
Well Location  
CHURCH  
District  
WETZEL  
County  
8274  
Well No.  
W.G. SNODGRASS  
Farm

STATE INSPECTOR SUPERVISING PLUGGING \_\_\_\_\_


AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:  
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 11<sup>th</sup> day of March, 2022 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
	Cleaned the hole with a 12 1/4" bit from the surface to 225'. Reduced the hole to 9 7/8" at 225'. Cleaned the hole with a 9 7/8" bit from 225' to 1243'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1009.2' - 1015.9'). Left 20' of 16" conductor pipe in the hole from the surface to 20'.  <b>Cemented the hole from 1243' to surface as follows:</b> From 1243' to 809' with 245 sacks of Thixotropic Cement with Green Dye and a gas blocker additive. Tagged the top of the Thixotropic plug at 809'. Cemented the hole from the top of the Thixotropic cement plug at 809' to the surface with 455 sacks of Expandable Cement. Cement did circulate at the surface. A total 700 sacks of cement were used to fill the hole from 1243' to the surface.	16" Conductor	0'	20'
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>1009.2' - 1015.9'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 23<sup>rd</sup> day of March, 2022

And further deponents saith not.



Matthew A. Yearsley  
Matthew A. Yearsley

Kevin S. Wright  
Kevin S. Wright

Sworn to and subscribed before me this 29<sup>th</sup> day of Mar, 2022

[Signature]  
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03485  
Well No. 8274  
Latitude: 39° 39' 35.83"N  
Longitude: -80° 24' 52.72"W