

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B. W. Peterson Operator Well No.: 7276

LOCATION: Elevation: 1207.3' Quadrangle: Big Run W.VA
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 30 Min. 08.19 Sec.
Longitude: _____ Feet West of -80 Deg. 31 Min. 31.73 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources Inc. Coal Operator West Virginia Land Resources Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
or Owner _____
Permit Issued Date 03/07/2022

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 3rd day of June, 2022, and the well was plugged and filled in the following manner:


| TYPE | FROM | TO | PIPE REMOVED | LEFT |
|--|---------|---------|--------------|---------|
| Thixotropic w/ Green Dye and Gas Block | 1228' | 821' | | |
| Expandable Cement | 821' | Surface | | |
| 8 5/8" Casing | 1038' | Unknown | 0' | Unknown |
| 16" Conductor | Surface | 20' | 0' | 20' |
| | | | | |
| | | | | |

Description of monument: 77" of 7" casing with company name, API #, well #, and date cemented and that the work of plugging and filling said well was completed on the 30th day of June, 2022.

And further deponents saith not. Matthew A. Yearsley

Kevin S. Wright

Sworn and subscribe before me this 8 day of August, 2022



My commission expires: June 8, 2027

Christopher Willis
Notary Public

Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

COASTAL FOREST RESOURCES COMPANY
Lease or Property Owner
P.O. BOX 1023 HAVANA, FL 32333
Address

WEST VIRGINIA LAND RESOURCES INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
BIG RUN W.VA
Well Location
GRANT
District
WETZEL
County
7276
Well No.
B.W. PETERSON
Farm

STATE INSPECTOR SUPERVISING PLUGGING _____

AFFIDAVIT

STATE OF WEST VIRGINIA,

County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 3rd day of June, 2022 and that the well was plugged in the following manner:

| Sand or Zone Record Formation | Filling Material | Casing/Tubing Size | Casing Pulled | Casing Left In |
|-------------------------------|--|--|---------------|----------------|
| | Cleaned the hole with a 12 1/4" bit from the surface to 67'. Reduced the hole to 9 7/8" at 67'. Cleaned the hole with a 9 7/8" bit from 67' to 1035'. Reduced the hole to 6 1/4" at 1035'. Cleaned the hole with a 6 1/4" bit from 105' to the top of the existing 8 5/8" casing at 1038'. Cleaned out the existing 8 5/8" casing with a 6 1/4" bit from 1038' to 1229'. Attempted to pull the 8 5/8" casing from 1038' by pulling 150% of the string weight but all attempts were unsuccessful. Left an unknown amount of 8 5/8" casing in the hole from 1038' to an unknown depth. Cut the remaining 8 5/8" casing at 1228', 1178', 1128', and 1078'. Cleaned a 9 7/8" hole through Pittsburgh Coal Seam (1021' - 1029'). Left 20' of 16" conductor in the hole from the surface to 20'. | 8 5/8" Casing 16" Conductor | 0' 0' | Unknown 20' |
| Coal Seams | | Description of Monument | | |
| <u>Pittsburgh</u> | <u>1021' - 1029'</u> | 77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level. | | |
| | | | | |
| | | | | |

... and that the work of plugging and filling said well was completed on the 30th day of June, 2022

And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

Sworn to and subscribed before me this 8 day of August, 2022

Christopher Andrew Willis
Notary Public

My commission expires: June 8, 2027

Permit No. 47-103-03487
Well No. 7276
Latitude: 39° 30' 08.19"N
Longitude: -80° 31' 31.73"W

