

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Robert Smith Operator Well No.: 7279

LOCATION: Elevation: 1335.3' Quadrangle: Big Run W.VA

District: Grant County: Wetzel

Latitude: _____ Feet South of 39 Deg. 30 Min. 06.60 Sec.

Longitude: _____ Feet West of -80 Deg. 30 Min. 56.63 Sec.

Well Type: OIL X GAS _____

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554

Agent David Roddy Coal Operator _____
or Owner _____

Permit Issued Date 09/06/2022

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 21st day of September, 2022, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1378'	971'	16" Conductor - 0'	23'
Expandable Cement	971'	Surface		

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 12th day of October, 2022.


And further deponents saith not. Matthew A. Yearsley

Kevin S. Wright

Sworn and subscribe before me this 4 day of November, 2022

My commission expires: June 8, 2027

Christopher Andrew Willis
Notary Public



Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
EDGAR D. & EDGAR D. BYARD JR.
Lease or Property Owner
2198 DEAD FALL RD. SMITHFIELD, WV 26562
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
BIG RUN W.VA
Well Location
GRANT
District
WETZEL
County
7279
Well No.
ROBERT SMITH
Farm

STATE INSPECTOR SUPERVISING PLUGGING _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 21st day of September, 2022 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
	Cleaned a 12 1/4" hole from the surface to 237'. Reduced the hole to 9 7/8" at 237'. Cleaned a 9 7/8" hole from 237' to 1364'. Reduced the hole to 6 1/4" at 1364'. Cleaned a 6 1/4" hole from 1364' to 1378'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1171.3' - 1177.4'). <u>Cemented the hole from 1378' to the surface as follows:</u> From 1378' to 971' with 200 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic cement plug at 971'. Cemented the hole from 971' to the surface with 520 sacks of Expandable Cement. Cement did circulate at the surface. A total of 720 sacks of cement were used to fill the hole from 1378' to the surface.	16" Conductor	0'	23'
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	1171.3' - 1177.4'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 12th day of October, 2022

And further deponents saith not.



Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

Sworn to and subscribed before me this 4 day of November, 2022

[Signature]
Notary Public

My commission expires: June 8, 2027

Permit No. 47-103-03533
Well No. 7279
Latitude: 39° 30' 06.60"N
Longitude: -80° 30' 56.63"W