

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: J.L. Stevens Operator Well No.: 7703

LOCATION: Elevation: 1141.7' Quadrangle: Big Run W.VA
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 30 Min. 56.24 Sec.
Longitude: _____ Feet West of -80 Deg. 30 Min. 35.64 Sec.

Well Type: OIL X GAS _____

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554

Agent David Roddy Coal Operator _____
Permit Issued Date 12/15/2022 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 19th day of April, 2023, and the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1201'	749'	7" Casing - 0'	Unknown - Cut at 1155'
Expandable Cement	749'	Surface	10 3/4" Casing - 0'	41'
			16" Conductor - 0'	16'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 12th day of May, 2023.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright

Sworn and subscribe before me this 5th day of JUN, 2023

My commission expires: 09/15/27 [Signature]
Notary Public



Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554

DOUGLAS JOE SMITH
Lease or Property Owner
403 PICKENPAUGH RD. SMITHFIELD, WV 26437

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554

Complete Address

BIG RUN W.VA

Well Location

GRANT

District

WETZEL

County

7703

Well No.

J.L. STEVENS

Farm

STATE INSPECTOR SUPERVISING PLUGGING _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 19th day of April, 2023 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned a 12 1/4" hole from the surface to 353'. Cleaned a 9 7/8" hole from 353' to top of existing 10 3/4" casing at 541'. Continue to clean 9 7/8" hole from 541' to top of existing 7" casing at 1135'. Cleaned a 6 1/4" hole from 1135' to 1201'. Cut 7" casing at 1155'. A diligent effort was made to remove existing 7" casing by pulling 150% of the string weight but all attempts were unsuccessful. Left an unknown amount of 7" casing in the hole from 1135' to an unknown depth. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (949' - 955'). Left 41' of 10 3/4" casing in the hole from 541' to 582'. Left 16' of 16" casing in the hole from the surface to 16'.		7" Casing	0'	Unknown
		10 3/4" Casing	0'	41'
		16" Conductor	0'	16'
Cemented the hole from 1201' to the surface as follows:				
From 1201' to 749' with 200 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic Cement plug at 749'. Cemented the hole from 749' to the surface with 380 sacks of Expandable Cement. Cement did circulate at the surface. A total of 580 sacks of cement were used to fill the hole from 1201' to the surface.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>949' - 955'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 12th day of May, 2023

And further deponents saith not.



Sworn to and subscribed before me this 5th day of Jun, 2023

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

[Signature]

Notary Public

My commission expires: 09/15/27

Permit No. 47-103-03541
Well No. 7703
Latitude: 39° 30' 56.24"N
Longitude: -80° 30' 35.64"W