

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: S & S Barker Operator Well No.: 7284

LOCATION: Elevation: 1141.7' Quadrangle: Big Run W.VA
District: Grant County: Wetzel
Latitude: _____ Feet South of 39 Deg. 30 Min. 16.56 Sec.
Longitude: _____ Feet West of -80 Deg. 31 Min. 20.47 Sec.

Well Type: OIL X GAS _____

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 02/16/2023 or Owner _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 16th day of May, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1250'	760'	7" Casing - 0'	Unknown - Multiple cuts placed in remaining casing
Expandable Cement	760'	Surface	16" Conductor - 0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 1st day of June, 2023.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright



Sworn and subscribe before me this 13th day of Jun, 2023

My commission expires: 09/15/27
Thomas J. Sullivan
Notary Public

Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

JOHN W. SHRIVER ETAL
Lease or Property Owner
704 GREENWOOD MANOR CIR MELBOURNE, FL 32904
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554

Complete Address
BIG RUN W.VA
Well Location

GRANT

District

WETZEL

County

7284

Well No.

S & S BARKER

Farm

STATE INSPECTOR SUPERVISING PLUGGING _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 16th day of May, 2023 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned a 12 1/4" hole from the surface to 278'. Cleaned a 9 7/8" hole from 278' to top of existing 7" casing at 326'. Cleaned a 6 1/4" hole from 326' to 1250'. Cut 7" casing at 1166' and 860'. A diligent effort was made to remove existing 7" casing by pulling 150% of the string weight but all efforts were unsuccessful. Left an unknown amount of 7" casing in the hole from 326' to an unknown depth. Cut remaining 7" casing at 1116', 1066', 1016', 976', 971', 966', 964', 962', 960.5', 955.5', 950.5' and 910.5'. Cleaned a 6 1/4" hole through the Pittsburgh Coal Seam (960.5' - 966.0'). Left 20' of 16" casing in the hole from the surface to 20'.		7" Casing 16" Conductor	0' 0'	Unknown 20'
<u>Cemented the hole from 1250' to the surface as follows:</u> From 1250' to 760' with 100 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic Cement plug at 760'. Cemented the hole from 760' to the surface with 400 sacks of Expandable Cement. Cement did circulate at the surface. A total of 500 sacks of cement were used to fill the hole from 1250' to the surface.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	960.5' - 966.0'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 1st day of June, 2023

And further deponents saith not.



Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

Sworn to and subscribed before me this 13th day of Jun, 2023

[Signature]

Notary Public

My commission expires: 09/15/27

Permit No. 47-103-03555
Well No. 7284
Latitude: 39° 30' 16.56"N
Longitude: -80° 31' 20.47"W