

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: T.J. Dawson Operator Well No.: 8360

LOCATION: Elevation: 1351.7' Quadrangle: Hundred W.VA, PA
District: Church County: Wetzel
Latitude: _____ Feet South of 39 Deg. 39 Min. 38.61 Sec.
Longitude: _____ Feet West of -80 Deg. 24 Min. 19.62 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
or Owner _____
Permit Issued Date 02/23/2023

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 27th day of April, 2023, and the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1402'	988'	8 5/8" Casing - 105'	73'
Expandable Cement	988'	Surface	16" Conductor - 0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 12th day of May, 2023.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright

Sworn and subscribe before me this 7th day of July, 2023

My commission expires: June 8, 2027
Christopher Andrew Willis
Notary Public



Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
MARLENE K. SHUMAN
Lease or Property Owner
12759 MASON DIXON HWY BURTON, WV 26562
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
HUNDRED W.VA, PA
Well Location
CHURCH
District
WETZEL
County
8360
Well No.
T.J. DAWSON
Farm

STATE INSPECTOR SUPERVISING PLUGGING _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 27th day of April, 2023 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
	Cleaned a 12 1/4" hole from the surface to 335'. Cleaned a 9 7/8" hole from 335' to the top of the existing 8 5/8" casing at 1214'. Cleaned a 7 7/8" hole from 1214' to 1402'. Removed 105' of 8 5/8" casing from 1214' to 1319'. A diligent effort was made to remove the remaining 8 5/8" casing by pulling 150% string weight but all efforts were unsuccessful. Left 73' of 8 5/8" casing in the hole from 1319' to 1392'. Cut the remaining 8 5/8" casing at 1344'. Cleaned a 9 7/8" hole from 1214' to the top of the remaining 8 5/8" casing at 1319'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1188.5' - 1194.0'). Left 20' of 16" conductor pipe in the hole from the surface to 20'.	8 5/8" Casing 16" Conductor	105' 0'	73' 20'
	Cemented the hole from 1402' to the surface as follows: From 1402' to 988' with 185 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic cement plug at 988'. Cemented the hole from 988' to the surface with 520 sacks of Expandable Cement. Cement did circulate at the surface. A total of 705 sacks of cement were used to fill the hole from 1402' to the surface.			
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	1188.5' - 1194.0'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 12th day of May, 2023

And further deponents saith not.

Matthew A. Yearsley
Matthew A. Yearsley


Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 7th day of July, 2023

Christopher Willis
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-103-03562
Well No. 8360
Latitude: 39° 39' 38.61"N
Longitude: -80° 24' 19.62"W