

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: J. Dawson Operator Well No.: 8191

LOCATION: Elevation: 1260' Quadrangle: Hundred WV, PA
District: Church County: Wetzel
Latitude: _____ Feet South of 39 Deg. 39 Min. 37.83 Sec.
Longitude: _____ Feet West of -80 Deg. 24 Min. 06.96 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 02/27/2023 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 6th day of June, 2023, and the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1302'	995'	8 5/8" Casing - 453'	Unknown
Expandable Cement	995'	Surface	16" Conductor - 0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 30th day of June, 2023.

And further deponents saith not. Matthew A. Yearsley
Kevin S. Wright

Sworn and subscribe before me this 11th day of July, 2023

My commission expires: June 8, 2027 Christopher Willis
Notary Public



Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

JOHN W. HAYES
Lease or Property Owner
12611 MASON DIXON HIGHWAY BURTON, WV 26562
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address

HUNDRED W.VA, PA
Well Location
CHURCH
District
WETZEL
County
8191
Well No.
J. DAWSON
Farm

STATE INSPECTOR SUPERVISING PLUGGING _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 6th day of June, 2023 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
	Cleaned a 12 1/4" hole from the surface to 326'. Cleaned a 9 7/8" hole from 326' to the top of the existing 8 5/8" casing at 640'. Cleaned a 7 7/8" hole through the 8 5/8" casing from 640' to 1302'. Cleaned a 7 7/8" hole through the Pittsburgh Coal Seam (1095' – 1101). Removed 453' of 8 5/8" casing from 640' to 1093'. A diligent effort was made to remove the remaining 8 5/8" casing by pulling 150% string weight but all efforts were unsuccessful. Left an unknown amount of 8 5/8" casing in the hole from 1093' to unknown depth. Cut the remaining 8 5/8" casing at 1300', 1250', 1200' and 1150'. Perforated the remaining 8 5/8" casing through the Pittsburgh Coal Seam with 4 shots at each of the following depths: 1101', 1098' and 1095'. The remaining 8 5/8" casing was parted from 1105' to 1112' and was previously ripped from 1171' to 1163'. Left 20' of 16" conductor pipe in the hole from the surface to 20'.	8 5/8" Casing 16" Conductor	453' 0'	Unknown 20'
	Cemented the hole from 1302' to the surface as follows: From 1302' to 995' with 190 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic cement plug at 995'. Cemented the hole from 995' to the surface with 575 sacks of Expandable Cement. Cement did circulate at the surface. A total of 765 sacks of cement were used to fill the hole from 1302' to the surface.			
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>1095' – 1101'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 30th day of June, 2023

And further deponents saith not.


Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

Sworn to and subscribed before me this 11th day of July, 2023



Christopher Willis
Notary Public

My commission expires:

June 8, 2027

Permit No. 47-103-03566
Well No. 8191
Latitude: 39° 39' 37.83"N
Longitude: -80° 24' 06.96"W