

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Lindsey Stewart Operator Well No.: 7426

LOCATION: Elevation: 1279' Quadrangle: Big Run W.VA  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 31 Min. 00.91 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 31 Min. 30.01 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 06/01/2023 or Owner \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 7th day of August, 2023, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Block	1378'	887'	7" Casing - 291'	Unknown
Expandable Cement	887'	Surface	8 5/8" Casing - 322'	Unknown
			16" Conductor - 0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 22nd day of August, 2023.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 18th day of September, 2023

My commission expires: June 8, 2027

Christopher Andrew Willis  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: \_\_\_\_\_ Title: \_\_\_\_\_



AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
SARA J. GOODRICH ETAL  
Lease or Property Owner  
433 BUCK RUN RD. SMITHFIELD, WV 26437  
Address

WEST VIRGINIA LAND RESOURCES INC  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
BIG RUN W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
7426  
Well No.  
LINDSEY STEWART  
Farm

STATE INSPECTOR SUPERVISING PLUGGING \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 7<sup>th</sup> day of August, 2023 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
<p>Cleaned a 12 1/4" hole from the surface to 515'. Cleaned a 9 7/8" hole from 515' to the top of the existing 8 5/8" casing at 971'. Cleaned a 7 7/8" hole from 971' to the top of the existing 7" casing at 1027'. Cleaned a 6 1/4" hole from 1027' to 1378'. Removed 291' of 7" casing from 1027' to 1318'. Left an unknown amount of 7" casing in the hole from 1318' to an unknown depth. Removed 322' of 8 5/8" casing from the 971' to 1293'. Left an unknown amount of 8 5/8" casing in the hole from 1293' to an unknown depth. Cleaned a 9 7/8" hole from 971' to the top of the remaining 8 5/8" casing at 1293'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1087' - 1093'). Cleaned a 7 7/8" hole from 1293' to the top of the remaining 7" casing at 1318'. Cleaned a 6 1/4" hole from 1318' to 1378'. Left 20' of 16" conductor pipe in the hole from the surface to 20'.</p> <p><b>Cemented the hole from 1378' back to the surface as follows:</b> From 1378' to 887' with 250 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged top of Thixotropic cement plug at 887'. Cemented the hole from 887' to the surface with 585 sacks of Expandable Cement. Cement did circulate at the surface. A total of 835 sacks of cement were used to fill the hole from 1378' to the surface.</p>	7" Casing	291'	Unknown	
	8 5/8" Casing	322'	Unknown	
	16" Conductor	0'	20'	
<b>Coal Seams</b>	<b>Description of Monument</b>			
<u>Pittsburgh</u>	<u>1087' - 1093'</u>	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 22<sup>nd</sup> day of August, 2023

And further deponents saith not.

Matthew A. Yearsley  
Matthew A. Yearsley


Kevin S. Wright  
Kevin S. Wright

Sworn to and subscribed before me this 18<sup>th</sup> day of September, 2023

Christopher Andrew Willis  
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-103-03582  
Well No. 7426  
Latitude: 39° 31' 00.91"N  
Longitude: -80° 31' 30.01"W