

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B W Peterson 83 Operator Well No.: 7336

LOCATION: Elevation: 1380.72' Quadrangle: Big Run WV
District: Grant County: Wetzel
Latitude: 39.5231 Feet South of 39 Deg. 31 Min. 23.39 Sec.
Longitude: -80.5277 Feet West of -80 Deg. 31 Min. 39.82 Sec.

Well Type: OIL GAS

Company West Virginia Land Resources INC. Coal Operator West Virginia Land Resources INC.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Coal Operator _____
Agent David Roddy or Owner _____
Permit Issued Date 8/23/24 _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:


Mathew A. Yearsley and Delbert Moore being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 15th day of August, 2024, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye and Gas Blocker	1365'	951	8 5/8" - 0'	Unknown
Expanding Cement	951	Surface	16" Conductor - 0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date completed and that the work of plugging and filling said well was completed on the 20th day of September, 2024.

And further deponents saith not. Matthew A. Yearsley
Delbert Moore

Sworn and subscribe before me this 25th day of September, 2024



My commission expires: June 8, 2027

Christopher Willis
Notary Public

Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES, INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

DALLISON LUMBER INC
Lease or Property Owner
PO BOX 159 JACKSONBURG WV 26377
Address

WEST VIRGINIA LAND RESOURCES, INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address

BIG RUN, WV
Well Location
GRANT
District
WETZEL
County
7336
Well No.

B W PETERSON 83
Farm

STATE INSPECTOR SUPERVISING PLUGGING Steve McCoy

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:

MATTHEW A. YEARSLEY and DELBERT MOORE being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 15th day of August, 2024 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
		8 5/8" Casing	0'	Unknown
		16" Conductor Casing	0'	20'
<p>Cleaned a 12 1/4" hole from surface to 836'. Reduced hole size to 7 7/8" at 836'. Cleaned a 7 7/8" hole from 836' to 1365'. Cleaned a 7 7/8" hole through the Pittsburgh Coal Seam (1151' - 1158'). A diligent effort was made to remove the 8 5/8" casing by pulling 150% of string weight. All attempts were unsuccessful. Left an unknown amount of 8 5/8" casing from 836' to an unknown depth. The 8 5/8" casing was cut at the following depths: 1358', 1308', 1258', 1208', 1168', 1163', 1158', 1155.5', 1153', 1151', 1146', 1141', 1101', 1051'. Left 20' of 16" conducting in hole from surface to 20'.</p> <p>Cemented Hole from 1365' to surface as follows: Cemented from 1365' to 951' with 120 sacks of Thixotropic Cement with Green Dye and Gas Blocker Additive. Cemented 951' to surface with 775 sacks of Expanding Cement. Cement did circulate at surface. A total of 895 sacks were used to fill the hole from 1365' to surface.</p>				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	1151' - 1158'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 20th day of September, 2024

And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley

Delbert Moore


Delbert Moore

Sworn to and subscribed before me this 25th day of September, 2024

[Signature]
Notary Public

My commission expires:

June 8, 2027



Permit No. 47-103-03679
Well No. 7336
Latitude: 39° 31' 23.39"N
Longitude: -80° 31' 39.82"W