

**STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS**

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B W Peterson 50 Operator Well No.: 7806

LOCATION: Elevation: 1260.39' Quadrangle: Big Run WV
District: Grant County: Wetzel
Latitude: 39.52334 Feet South of 39 Deg. 31 Min. 24.0126 Sec.
Longitude: -80.52976 Feet West of 80 Deg. 31 Min. 47.1500 Sec.

Well Type: OIL X GAS

Company	West Virginia Land Resources, Inc	Coal Operator	West Virginia Land Resources, Inc
	1 Bridge Street	or Owner	1 Bridge Street
	Monongah, WV 26554		Monongah, WV 26554
Agent	David Roddy	Coal Operator	
Permit Issued Date	08/29/24	or Owner	

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:

Matthew Yearsley and Delbert Moore being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 25th day of September, 2024, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Theotropic w/ Green Dye and Gas Blocker	1300'	827'	7" Casing - 0'	Unknown
Expandable	827'	Surface	16" Conductor Casing - 0'	20'

Description of monument: 7" of 7" casing with Company Name, Well #, API #, and Date Completed and that the work of plugging and filling
said well was completed on the 7th day of October, 2024.

And further deponents saith not. **Matthew A Yearsley**


Delbert Moore

Sworn and subscribe before me this 30 day of October, 2024

My commission expires: August, 13, 2029  James McCormick
Digital Signature

Affidavit reviewed by the Office of Oil and Gas: **Mcco** Date: 2024.11.04 07:56:29
-05'00'

Title:



RECEIVED
Office of Oil and Gas

SEP 08 2025

WV Department of
Environmental Protection

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
DALLISON LUMBER, INC
Lease or Property Owner
PO BOX 159 JACKSONBURG, WV 26377
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
Big Run WV
Well Location
GRANT
District
WETZEL
County
7806
Well No.
B W PETERSON 50
Farm

STATE INSPECTOR SUPERVISING PLUGGING STEVE MCCOY

Stephen McCoy

Digitally signed by Stephen
McCoy
Date: 2024.11.04 07:56:06 -05'00'

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of WETZEL ss:

MATTHEW A. YEARSLEY and DELBERT MOORE being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by WEST VIRGINIA LAND RESOURCES, INC. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 25th day of September, 2024 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned a 12 1/4" Hole from surface to 315'. Reduced to 9 7/8" bit and cleaned a 9 7/8" hole from 315' to 528 to the top of 7" casing found at 528'. Reduced to 6 1/2" bit and cleaned a 6 1/4" hole from 528' to 1300'. Cleaned a 6 1/2" hole through the Pittsburgh Coal Seam (1027' – 1034'). A diligent effort was made to remove the 7" casing by pulling 150% of the sting weight. All attempts were unsuccessful. Left an unknown amount of 7" casing from 528' to unknown depth. Cut the 7" casing at the following depths, 1027', 1028', 1030', 1032', 1034'. Perforated the 7" casing with 6 shots at the following depths: 1234', 1184', 1134', 1084', 1044', 1039', 1022', 1017', 977', 927'.		7" Casing 16" Conductor Casing	0' 0'	Unknown 20'
<u>Cemented hole from 1300' to surface as follows:</u> Cemented hole from 1300' to 827' using 100 sacks of Thixotropic Cement with Green Dye and Gas Blocker Additive. Cemented hole from 827' to surface using 450 sacks of Expandable Cement. Cement did circulate at the surface. A total of 550 sacks of cement were used to fill the hole from 1300' to the surface.				
Coal Seams		Description of Monument		
Pittsburgh	1027' – 1034'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 7th day of October, 2024

And further deponents saith not.

Matthew A. Yearsley

Matthew A. Yearsley


Delbert Moore

Delbert Moore

Sworn to and subscribed before me this 30 day of October

My commission expires:

August 13, 2029



Notary Public
Permit No. 47-103-03680
Well No. 7806
Latitude: 39° 31' 24.01"N
Longitude: -80° 31' 47.15"W
SEP 08 2025
WV Department of Environmental Protection