

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Gilbert 1 Operator Well No.: 7308

LOCATION: Elevation: 1056.43 Quadrangle: Big Run WV  
District: Grant County: Wetzel  
Latitude: 39.52127 Feet South of 39 Deg. 31 Min. 16.5697 Sec.  
Longitude: -80.53322 Feet West of 80 Deg. 31 Min. 59.5976 Sec.

Well Type: OIL        GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554

Agent David Roddy Coal Operator         
Permit Issued Date 02/03/25 or Owner       

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Wetzel ss:

Matthew Yearsley and Thomas Thrasher being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 8th day of April, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable Cement	1023'	616'	7" Casing - 265'	Unknown
	616'	Surface	16" Conductor Casing - 0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date completed and that the work of plugging and filling said well was completed on the 25th day of April, 2025.

And further deponents saith not. Matthew A. Yearsley

Thomas Thrasher

Sworn and subscribe before me this 29th day of May, 2025


My commission expires: August 13, 2029

Stephen McCormick

Notary Public  
Digitally signed by Stephen  
McCoey  
Date: 2025.05.30 09:32:47  
-04'00

Affidavit reviewed by the Office of Oil and Gas: Stephen McCoey

Title:       



RECEIVED  
Office of Oil and Gas  
MAY 30 2025

WV Department of  
Environmental Protection  
06/13/2025

WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OIL AND GAS WELLS DIVISION

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES, INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
COASTAL FOREST RESOURCES CO  
Lease or Property Owner  
8007 FLORIDA GEORGIA HWY, HAVANA, FL 32333  
Address

WEST VIRGINIA LAND RESOURCES, INC.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
Big Run WV  
Well Location  
GRANT  
District  
WETZEL  
County  
7308  
Well No.  
GILBERT 1  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Steve McCoy  
AFFIDAVIT

Stephen McCoy  
Digitally signed by Stephen McCoy  
Date: 2025.05.30 09:32:31 -04'00'


STATE OF WEST VIRGINIA,  
County of WETZEL ss:

MATTHEW A. YEARSLEY and THOMAS THRASHER being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 8<sup>th</sup> day of April, 2025 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Placed cuts in 7" casing at 1023' and 816.5'. Pulled 265' of 7" casing from the surface. Cleaned a 12 1/4" hole from surface to 192'. Reduced to 9 7/8" bit and cleaned 9 7/8" hole from 192' to 265'. Reduced to 6 1/4" bit and cleaned 6 1/4" hole inside the 7" casing from 265' to 1023'. Cleaned a 6 1/4" hole through the Pittsburgh Coal Seam (816.5' – 823'). Made a diligent effort to remove additional 7" casing by pulling 150% of the string weight. All attempts were unsuccessful. Left an unknown amount of 7" casing in the hole from 265' to an unknown depth. Cut the 7" casing at 973', 923', 873', 833', 828', 823', 821.7', 819.74', 818.11', 811.5', 806.5', 766.5', and 716.5'. Perforated the 7" casing at 823', 821.7', 818.11' using 6 shots at each location. <b>Cemented hole from 1023' to surface as follows:</b> Cemented hole from 1023' to 616' using 85 sacks of Thixotropic Cement with Green Dye and Gas Blocker Additive. Cemented hole from 616' to surface using 220 sacks of Expandable Cement. A total of 305 sacks of cement were used to fill the hole from 1023' to surface. Cement did circulate at the surface.	7" Casing  16" Conductor Casing	265'  0'	Unknown  20'	
Coal Seams		Description of Monument		
Pittsburgh	816.5' – 823'	77' of 7" casing w/ company name, well #, API # and date cemented stated on 7" casing. Well marker will be attached to cement plug at around level.		

... and that the work of plugging and filling said well was completed on the 25<sup>th</sup> day of April, 2025

And further depose and say



Sworn to and subscribed before me this 29<sup>th</sup> day of May 2025

My commission expires:

August 13, 2029

Matthew A. Yearsley  
Matthew A. Yearsley

Thomas Thrasher  
Thomas Thrasher

Stephen McCoy  
Notary Public

RECEIVED  
Office of Oil and Gas

MAY 30 2025

Permit No. 47-103-03717  
Well No. 7308  
Latitude: 39° 31' 16.57"N  
Longitude: -80° 31' 59.60"W

WV Department of  
Environmental Protection

06/13/2025