

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: J.L. Stevens Operator Well No.: 7487

LOCATION: Elevation: 1,355.60' Quadrangle: Big Run, WV
District: Grant County: Wetzel
Latitude: 39.517605 Feet South of 39 Deg. 31 Min. 3.378 Sec.
Longitude: -80.511887 Feet West of 80 Deg. 30 Min. 42.793 Sec.

Well Type: OIL _____ GAS X

Company	<u>West Virginia Land Resources</u>	Coal Operator	<u>West Virginia Land Resources</u>
	<u>1 Bridge Street</u>	or Owner	<u>1 Bridge Street</u>
	<u>Monongah, WV 26554</u>		<u>Monongah, WV 26554</u>
Agent	<u>David Roddy</u>	Coal Operator	_____
Permit Issued Date	<u>2-13-25</u>	or Owner	_____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:

Matthew Yearsley and Thomas Thrasher being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 20th day of June, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Therapeutic w/ Green Dye & Gas Block	1,365'	858'	7" Casing - None	Unknown
Expandable	858'	Surface	16" Conductor - None	11'


Description of monument: 77' of 7" casing with company name, well #, API #, and date completed and that the work of plugging and filling said well was completed on the 7th day of July, 2025.

And further deponents saith not. Matthew A. Yearsley

Thomas Thrasher

Sworn and subscribe before me this 21st day of August, 2025

My commission expires: August 13, 2029 Kerri A McCormick
Notary Public



Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

DOUGLAS JOE SMITH
Lease or Property Owner
4464 Mannington Rd Smithfield, WV 26437
Address

WEST VIRGINIA LAND RESOURCES
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address

Big Run, WV 7.5'
Well Location
GRANT
District
WETZEL
County
7487
Well No.
J.L. STEVENS
Farm

STATE INSPECTOR SUPERVISING PLUGGING Steve McCoey


AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:
MATTHEW A. YEARSLEY and Thomas Thrasher being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 20th day of June, 2025 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned out 7" casing with 6 1/4" bit from surface to 1,194'. Reduced bit and cleaned hole with 2 3/8" stinger from 1,194' to 1,365'. Perforated 7" casing at 1,363', 1,313', 1,263', and 1,213' with 6 shots at each location. Cut 7" casing at 1,173'. Made a diligent effort to pull 7" casing from surface to 1,173' by pulling 150% of string weight with no success. All attempts to remove remaining casing were unsuccessful. Perforated 7" casing with 6 shots each at 1,168', 1,163', 1,161.25', 1,159.5', 1,157.75', 1,156', 1,151', 1,146', 1,106', and 1,056'. Pittsburg Coal Seam was from 1,158' to 1,163'.	7" Casing 16" Conductor	0 0	Unknown 11'	
<u>Cemented hole from 1,365' to surface as follows:</u> Cemented well from 1,365' to 858' using 105 sacks of Thixotropic Cement with Green Dye and Gas Blocker additive. Cemented from 858' to surface using 135 sacks of Expanding Cement. Used a total of 240 sacks of cement to fill the entire wellbore. Cement did circulate at surface. Left 11' of 16" conductor in hole from surface to 11'.				
Coal Seams		Description of Monument		
Pittsburgh	1,158' – 1,163'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 7th day of July, 2025

And further deponents do so not.



Matthew A. Yearsley
Matthew A. Yearsley

Thomas Thrasher
Thomas Thrasher

Sworn to and subscribed before me this 21st day of August 2029

Kerri A. McCormick
Notary Public

My commission expires:

August 13, 2029

Permit No. 47-103-03718
Well No. 7487
Latitude: 39° 31' 3.378"N
Longitude: 80° 30' 42.793"W