

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: J.L. Stevens 1 Operator Well No.: 7488

LOCATION: Elevation: 1079.4' Quadrangle: Big Run WV
District: Grant County: Wetzel
Latitude: 39.52158 Feet South of 39 Deg. 31 Min. 17.6869 Sec.
Longitude: -80.52531 Feet West of 80 Deg. 31 Min. 31.1095 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 02/13/25 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:

Matthew Yearsley and Thomas Thrasher being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 15th day of May, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thickness of Cement at Open Top and Gas Sealer	1007'	597'	3/4" Cable - 3280'	0'
Expandable Cement	597'	Surface	2 3/8" Tubing - 3280'	0'
			5 1/2" Casing - 1007'	Unknown
			7" Casing - 0'	Unknown
			20" Conductor Casing - 0'	10'

Description of monument: 77" of 7" casing with company name, well #, API #, and date completed and that the work of plugging and filling said well was completed on the 30th day of May, 2025.

And further deponents saith not. Matthew A. Yearsley


Thomas Thrasher

Sworn and subscribe before me this 11th day of June, 2025

My commission expires: August 13, 2029 Kerri A. McCormick
Notary Public

Stephen Mccoy Digitally signed by Stephen Mccoy
Date: 2025.06.18 08:50:58 -04'00'

Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____



RECEIVED
Office of Oil and Gas

SEP 08 2025

WV Department of
Environmental Protection

09/12/2025

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

DOUGLAS SMITH
Lease or Property Owner
4464 Mannington Rd., Smithfield, WV 26437
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address

Big Run WV
Well Location
GRANT
District
WETZEL
County
7488
Well No.

J.L. STEVENS 1
Farm
Stephen
McCoy

Digitally signed by Stephen
McCoy
Date: 2025.06.18 08:51:13
04'00"

STATE INSPECTOR SUPERVISING PLUGGING Steve McCoy
AFFIDAVIT


STATE OF WEST VIRGINIA,
County of **WETZEL** ss:

MATTHEW A. YEARSLEY and **THOMAS THRASHER** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 15th day of May, 2025 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Hooked and pulled 3280' of 2 3/8" tubing and 3/4" cable together leaving no tubing or cable in the hole. Cut 5 1/2" casing at 1007'. Pulled 1007' of 5 1/2" casing leaving an unknown amount of 5 1/2" casing in the hole. Cut 7" casing at 1005' and 805'. Made a diligent effort to pull 7" casing by pulling 150% of string weight. All attempts were unsuccessful. Left an unknown amount 7" casing in the hole. Cut 7" casing at 1005', 955', 905', 855', 815', 810', 803.13', 801.26', 799.39', 797.5', 792.5', 787.5', 474.5', and 967.5'. Cut 7" casing through the Pittsburgh Coal (797.5' - 805'). Cemented hole from 1007' to surface as follows: Cemented hole from 1007' to 597' using 85 sacks of Thixotropic Cement with Green Dye and Gas Blocker Additive. Cemented hole from 597' to surface using 150 sacks of Expandable Cement. A total of 235 sacks of cement were used to fill the hole from 1007' to surface. Cement did circulate at the surface.	3/4" Cable	3280'	0'	
	2 3/8" Tubing	3280'	0'	
	5 1/2" Casing	1007'	Unknown	
	7" Casing	0'	Unknown	
	16" Conductor Casing	0'	10'	
Coal Seams	Description of Monument			
Pittsburgh	797.5' - 805'	77" of 7" casing w/ company name, well #, API # and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 30th day of May, 2025

And further reports saith not



Matthew A. Yearsley
Matthew A. Yearsley

Thomas Thrasher
Thomas Thrasher

Sworn to and subscribed before me this 16th day of June 2025

Kerri A. McCormick
Notary Public

My commission expires:

August 13, 2029

Permit No. 47-103-03720
Well No. 7488
Latitude: 39° 31' 17.69"N
Longitude: 80° 31' 31.11"W

RECEIVED
Office of Oil and Gas

SEP 08 2025

WV Department of
Environmental Protection

09/12/2025