

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL


AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Tall Timber Inc. Operator Well No.: 7374

LOCATION: Elevation: 1299.43 Quadrangle: Big Run W.Va
District: Grant County: Wetzel
Latitude: 39.520996 Feet South of 39 Deg. 31 Min. 16.6 Sec.
Longitude: -80.514238 Feet West of 80 Deg. 30 Min. 51.2 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources, Inc Coal Operator West Virginia Land Resources, Inc
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 10/15/2025 or Owner _____



AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Wetzel ss:

Matthew Yearsley and Thomas Trasher being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 4th day of November, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
8 5/8" Casing	295'	Unknown Depth	0'	Unknown
16" Casing	19'	Surface	0	19'

Description of monument: 77' of 7" casing with Company name, Well #, API#, and Date Completed and that the work of plugging and filling said well was completed on the 1st day of Decemeber, 2025.

And further deponents saith not. Matthew A Yearsley
Thomas Thrasher



Sworn and subscribe before me this 16th day of January, 2026

My commission expires: August 13, 2029 Kerri McCormick

Stephen
Digitally signed by Stephen Mccoy
Date: 2026.01.27 11:11:03 -05'00'

Affidavit reviewed by the Office of Oil and Gas: Mccoy Title: _____


02/06/2026

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
JOSEPH SMITH (TALL TIMBER INC.)
Lease or Property Owner
4464 MANNINGTON RD, SMITHFILED WV 26437
Address

WEST VIRGINIA LAND RESOURCES
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
BIG RUN, WV 7.5'
Well Location
GRANT
District
WETZEL
County
7374
Well No.
J.W. NORRIS
Farm



STATE INSPECTOR SUPERVISING PLUGGING _____ Steve McCoy

Stephen Mccoy Digitally signed by Stephen Mccoy
Date: 2026.01.27 11:11:22 -05'00'

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Wetzel ss:

MATTHEW A. YEARSLEY and **THOMAS THRASHER** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 4th day of November, 2025 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned the hole with a 12 1/4" bit from surface to 95'. Reduced hole 95'. Cleaned the hole with a 9 7/8" bit from 95' to 295'. Tagged the top of the existing 8 5/8" casing at 295'. Cleaned out existing 8 5/8" casing from 295' to 1297' with a 6 1/4" bit. Cut 8 5/8" at 1084.5'. Made a diligent effort to remove 8 5/8" casing from 295' to 1084.5' by pulling 150% of string weight. All attempts were unsuccessful. Cleaned a 6 1/4" hole through the Pittsburg Coal Seam from 1077' to 1084.5'. Placed cuts in 8 5/8" casing with 8 shots each at 1284.5', 1082.6', and 1080.6'. Perforated 8 5/8" casing at 1234.5', 1184.5', 1134.5', 1094.5', 1089.5', 1078.79', 1077', 1072', 1067', 1027', and 977'. Cemented the hole from 1297' to Surface as follows: From 1297' to 877' using 125 sacks of Thixotropic Cement with green dye and gas blocker additive. From 877' to surface using 400 sacks of Expanding Cement. Placed a total of 525 sacks of cement in the well. Cement did circulate at surface. Left 19' of 16" conductor in the hole at surface	8 5/8" Casing 16" Conductor	None None	Unknown 19'	
Coal Seams		Description of Monument		
Pittsburgh	1,077' - 1,084.5'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said Well was completed on the 1ST day of December 2025

And further deponents saith not



Matthew A Yearsley

Matthew A. Yearsley

Thomas Thrasher

Thomas Thrasher

Sworn to and subscribed before me this 16th day of January 2026

Steph Mccoy
Notary Public

My commission expires:

August 13, 2029

Permit No. 47-103-03766
Well No. 7374
Latitude: 39° 52' 0.47" N
Longitude: 80° 51' 5.89" W

02/06/2026