

LAND OWNED BY: **GEO. E. RICE ET. AL. WAYNESBURG PA.**
S.W. MEALS EST. PITTSBURGH PA.

NEW LOCATION
 WELL DEEPER
 ABANDONMENT

VAUG - 8 1944

136-1-39 W
1.73 A

COMPANY **NATIONAL SUPPLY COMPANY**
 ADDRESS **LOGAN OHIO**
 NAME **SAMUEL FURBEE**
 ACT. "A" ACRES **126 1/4 (62 3/4)** LEASE NO.
 WELL (FARM) NO. **2** SERIAL NO. **9-(665)**
 ELEVATION (SPIRIT LEVEL) **1135'**
 TOWNSHIP **LITTLETON**
 COUNTY **WETZEL** DISTRICT **PROCTOR**
 ENGINEER *J. M. Moore*
 ENGINEER'S REGISTRATION NO.
 DATE **APRIL 11 1944** DRAWING NO. **U-1-271 (N)**
 SCALE **800'**

WC

STATE OF WEST VIRGINIA
 DEPARTMENT OF MINES
 OIL AND GAS DIVISION
 CHARLESTON

WELL LOCATION MAP
 FILE NO. **WET-478-A**

LOCATION OF WELL ON UNITED STATES TOPOGRAPHIC MAPS SCALE 1 TO 62,500. LATITUDE AND LONGITUDE AND ELEVATION REPRESENTED BY BORDER LINES OF MAP.

SPACES ONE INCH ON BORDER LINE REPRESENTS 800 FEET.



934

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

WELL RECORD

Permit No. 478 A Oil or Gas Well Oil
(KIND)


Company..... National Supply Company
Address..... Logan, Ohio
Farm..... Samuel Furbee Acres 126
Location (waters).....
Well No. 9-665 Elev. 1135 ft.
District Proctor County Wetzel
The surface of tract is owned in fee by.....
Address.....
Mineral rights are owned by National Supply Company
Address Logan, Ohio
Drilling commenced Sept. 13, 1922
Drilling completed Nov. 15, 1922
Date Shot 11/17/22 From 3170' To 3180'
With 15 Quarts
Open Flow /10ths Water in..... Inch
/10ths Merc. in..... Inch
Volume..... Cu. Ft.
Rock Pressure..... lbs..... hrs.
Oil..... bbls., 1st 24 hrs.
Fresh water..... feet..... feet
Salt water..... feet..... feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer.....
13			
10	518	137	Size of.....
8 1/4	1652'	1652'	
6 3/4	2153'	2153'	Depth set.....
5 3/16	2801'	2801'	
3			Perf. top.....
2	3190'	3190'	Perf. bottom.....
Liners Used.....			Perf. top.....
			Perf. bottom.....

CASING CEMENTED..... SIZE..... No. Ft..... Date
COAL WAS ENCOUNTERED AT 1131 FEET 24 INCHES
..... FEET..... INCHES..... FEET..... INCHES
..... FEET..... INCHES..... FEET..... INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Pittsburgh Coal			1131	1133			
Red Rock			1187	1431			
Little Dunkard			1466	1511			
Big Dunkard			1610	1660			
Gas Sand			1727	1745			
Maxon Sand			2085	2173			
Little Lime			2230	2238			
Big Lime			2248	2332			
Big Injun			2332	2545			
Slate			2545	2617			
Berea Grit			2617	2629			
Gantz Sand			2700	2750			
50 Foot Sand			2912	2921			
Slate			2921	2995			
30 Foot Sand			2995	3002			
Red Rock			3002	3085			
Slate			3085	3156			
Gordon Stray			3156	3160			
Slate			3160	3173			
Gordon Sand			3173	3180			
Total Depth				3197			

Oil 3176-3180



Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks

Date July 22, 1944

APPROVED The National Supply Company, Owner

By *M. Williams*, Agent
(Title)