



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

1279

836-A

WELL RECORD

Permit No. Well purchased from Hope Natural Gas Company. Oil or Gas Well "GAS"
(KIND)


Company Pittsburgh & West Va Gas Company.
Address Clarksburg, West Va.
Farm Elizabeth Kinble Acres 111
Location (waters) Harrington 1/4, 1-3
Well No. 3113 Elev. 1271 VA
District Clay County Wetzel
The surface of tract is owned in fee by Joe Hunt
Address Hod, Penn.,
Mineral rights are owned by Mary A. Renner et al.
Address Littleton, W. Va.
Drilling commenced July 23, 1910
Drilling completed August 24, 1910
Date Shot From To
With
Open Flow /10ths Water in Inch
/10ths Merc. in Inch
Volume Cu. Ft.
Rock Pressure lbs. hrs.
Oil bbls., 1st 24 hrs.
Fresh water feet feet
Salt water feet feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			
13			
10	303'	303'	Size of
8 1/2	1172'	1172'	
6 1/2	2167'	None.	Depth set
5 3/16			
3			Perf. top
2			Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED SIZE No. Ft. Date

COAL WAS ENCOUNTERED AT 643 FEET 36 INCHES
853 FEET 72 INCHES 971 FEET 84 INCHES
FEET INCHES FEET INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Un-recorded			0	643			
Native Coal			643	651			
Un-recorded			651	853			
M.F. Coal			853	859			
Un-recorded			859	971			
Fgh. Coal			971	978			
Un-recorded			978	1305			
Little Durkard			1305	1428			
Un-recorded			1428	1465			
Big Durkard			1465	1515			
Un-recorded			1515	1735			
Gas Sand			1735	?	Gas	1741'	
Un-recorded			?	1810			
Lat. Salt Sand			1810	1971			
Un-recorded			1971	2032			
Marion Sand			2032	2057			
Un-recorded			2057	2219			
Big Injun			2219	2464			
Un-recorded			2464	2557			
Barren			2557	2577			
Un-recorded			2577	2601			
Ganta Sand			2601	2654			
Un-recorded			2654	2777			
30 Ft. Sand			2777	2982			
Un-recorded			2982	3014			
Gordon Stray			3014	3049			
Gordon Sand			3049	3074			
Un-recorded			3074	3099			
4th Sand			3099	3130			
Un-recorded			3130	3154			
5th Sand			3154	3161	Gas	3159	
Un-recorded			3161	3212			
Total Depth				3212			



MAR 6 1950

Record of Well No. 5418 Located on Elizabeth Kimble Farm June 24th, 1910.
 Clay District Wetzel County West Va. State
 Division "T" District No. 11 Drilled under well Order
 Rig built by John Craig Began July 12th, 1910. Completed July 16th, 1910.
 Well drilled by G.W. Rowley Began July 29th, 1910. Completed August 24th, 1910.
 Depth of Well 3212 feet Size of Hole 6-5/8" Producing Gas
 2880 Top Bailer lost in hole by H N Geo Co
 Well purchased from the Hope Natural Gas Company, under agreement dated July 1st, 1939.

Elev: 1281

CASED WITH

REMARKS

AMOUNT	SIZE	KIND	REMARKS
303 Ft.	8"	10"	
1472 Ft.	8 1/2"	8 1/2" Steel shoe.	
2299 Ft.	2"	6-5/8"	Reclaimed
2170 Ft.	4"		

COAL VEINS Native 648 Mapletown 853 2760 1940 971
 651 Mapletown 859 B 2760 1940 978

FORMATIONS

NAME	TOP	BOTTOM	OIL	GAS	WATER	REMARKS
Native Coal	648	651				Steel Line run 648 Ft.
Mapletown Coal	853	859				
Pittsburgh Coal	971	978				Steel Line run 971 Ft.
Little Dunkard	1385	1418				" " " 1385 Ft.
Big Dunkard	1465	1515				" " " 1465 Ft.
Gas Sand	1735	1741.8		1741		" " " 1735 Ft.
First Salt	1810	1981				
Maxon Sand	2032	2057				
Big Injun	2219	2464				
Berea	2557	2577				
Gantz	2814	2834				
Thirty Feet	2977	2982				
Gordon Stray	3014	3048.				
Gordon	3048	3074				
Fourth Sand	3099	3130				
Fifth Sand	3154	3161		3159		
Total Depth		3212				

Well cleaned out Dec 1940
 Total Depth 2880 top Bailer lost in hole by H N Geo.