

NOTICE OF PROPOSED LOCATION OF OIL AND GAS WELL

(REQUIRED BY SECTION 2, CHAPTER 86, ACTS 1929)

WEST VIRGINIA DEPARTMENT OF MINES

OIL AND GAS SECTION

TO THE DEPARTMENT OF MINES,
Charleston, W. Va.

Burnt Hill Oil Co. Limited

BURNT HILL OIL COMPANY
C.E. LOVE, MANAGER

B. F. MAYO, Owner of land

COAL OPERATOR OR COAL OWNER

NAME OF WELL OPERATOR

Williamstown, W. VA

ADDRESS

Williamstown W.VA.

COMPLETE ADDRESS

No coal

COAL OPERATOR OR COAL OWNER

May 28, 1934

PROPOSED LOCATION

Williams

District

Wood

County

Well No. 1

B. F. MAYO

Farm

GENTLEMEN:

The undersigned well operator is entitled to drill upon the above named farm or tract of land for oil and gas, having fee title thereto, (or as the case may be) under grant or lease dated April 12

1934

made by B. F. & MINNIE MAYO

C. E. Love and E. C. Hartman

and recorded on the

not recorded yet

of, in the office of the County Clerk for said County in

Book, page

The enclosed plat was prepared by a competent engineer and shows the proposed location of a well to be drilled for oil and gas by the undersigned well operator on the farm and in the Magisterial District and County above named, determined by survey and courses and distances from two permanent points, or land marks.

The undersigned well operator is informed and believes there are no coal operators operating beds of coal beneath said farm or tract of land on which said well is located, or within 500 feet of the boundaries of the same, who have mapped their workings and filed their maps as required by law, excepting the coal operators or coal owners (if any) above named as addressees.

The above named coal operators or coal owners (if any) are notified that any objections they may desire to make to such proposed location, or which they are required to make by Section 3 of said Act, if the drilling of a well at said proposed location will cause a dangerous condition in or about their respective coal mines, must be received by, or filed with the Department of Mines within ten* days from the receipt of a copy of this notice and accompanying plat by said Department. Said coal operators are further notified that forms for use in making such objections will be furnished to them by the Department of Mines promptly on request and that all such objections must set forth as definitely as is reasonably possible the ground or grounds on which such objections are based and indicate the direction and distance the proposed location should be moved to overcome same.

(The next paragraph is to be completed only in Department's copy.)

Copies of this notice and the enclosed plat were mailed by registered mail, or delivered to the above

named coal operators or coal owners at their above shown respective address day before, or on the same day with the mailing or delivery of this copy to the Department of Mines at Charleston, West Virginia.

BURNT HILL OIL COMPANY

Very truly yours,

BY

C. E. Love

WELL OPERATOR

Address of Well Operator }

STREET

Williamstown, W. VA. 01/05/2024

CITY OR TOWN

W. VA.

STATE

*Section 3 If no such objections be filed, or be found by the department of mines, within said period of ten days from the receipt of said notice and plat by the department of mines, to said proposed location, the department shall forthwith issue to the well operator a drilling permit reciting the filing of such plat, that no objections have been made by the coal operators to the location, or found thereto by the department, and that the same is approved and the well operator authorized to proceed to drill at said location.

MAY 31 1934

W00-27

W00-27

NOTICE OF PROPOSED LOCATION OF OIL AND GAS WELL
WEST VIRGINIA DEPARTMENT OF MINES
OIL AND GAS SECTION

To The Department of Mines
Charleston, W. Va.

BURNETT HILL OIL COMPANY
C. E. LOVE, MANAGER

B. F. MAYO, Owner of Land

NAME OF WELL OPERATOR

COAL OPERATOR OR COAL OWNER

Williamstown, W. Va.

Williamstown, W. Va.

COMPLETE ADDRESS

ADDRESS

1931 MAY 28

NO COAL

PROPOSED LOCATION

COAL OPERATOR OR COAL OWNER

Williamstown

ADDRESS

Wood County

COAL OPERATOR OR COAL OWNER

Well No. 1

B. F. MAYO

ADDRESS

The undersigned well operator is entitled to drill upon the above named farm or tract of land for

oil and gas having the title thereto, (or as the case may be) under grant or lease dated

1931 made by B. F. & MINNIE MAYO

C. E. Love and E. C. Hartman and recorded on the

not recorded yet

in the office of the County Clerk for said County in

The enclosed plat was prepared by a competent engineer and shows the proposed location of a well to be drilled for oil and gas by the undersigned well operator on the farm and in the Mineral District and County above named, determined by survey and courses and distances from two permanent points or land marks.

The undersigned well operator is informed and believes there are no coal operators operating beds of coal beneath said farm or tract on which said well is located, or within 500 feet of the boundary of the same, who have mapped their workings and filed their maps as required by law, excepting the coal operators or coal owners (if any) above named as addressees.

The above named coal operators or coal owners (if any) are notified that any objections they may desire to make to such proposed location, or which they are required to make by Section 3 of said Act, if the drilling of a well at said proposed location will cause a dangerous condition in or about their respective coal mines, must be received by, or filed with the Department of Mines within ten days from the receipt of a copy of this notice and accompanying plat by said Department. Said coal operators are further notified that forms for filing such objections will be furnished to them by the Department of Mines promptly on request and that all such objections must set forth as definitely as is reasonably possible the grounds or grounds on which such objections are based and indicate the direction and distance the proposed location should be moved to overcome same.

(The next paragraph is to be completed only in Department's copy.)
Copies of this notice and the enclosed plat were mailed by registered mail, or delivered to the above

named coal operators or coal owners at their above shown respective addresses, on the same day with the mailing or delivery of this copy to the Department of Mines at Charleston, West Virginia.

BURNETT HILL OIL COMPANY

Very truly yours,

WELL OPERATOR

Address of Well Operator

Williamstown, W. Va.

CITY OR TOWN

W. Va.

STATE

Section 3. . . . If no such objections be filed or be found by the department of mines within said period of ten days from the receipt of said notice and plat by the department of mines to said proposed location, the department shall forthwith issue to the well operator a drilling permit, reciting the filing of such plat, that no objections have been made by the coal operators to the location, or terming thereto by the department, and that the same is approved and the well operator authorized to proceed to drill at said location.

01/05/2024

A 11

May 31, 1934

Mr. B. F. Mayo
Williamstown, W. Va.

Dear Sir:

A notice of a proposed location of oil or gas well No. 1 on the B. F. Mayo Farm, Williams District, Wood County, has been received from the Burnt Hill Oil Company, Williamstown, West Virginia. A copy of this notice with an attached map should have been mailed you by the well operator.

If, from the location of the above proposed well, it is apparent that your interests are not properly protected, you should file your objection on or before June 10, 1934.

Very truly yours,

Chief of Department of Mines.

NPR:g

01/05/2024

A-12

June 11, 1934

Burnt Hill Oil Company
c/o Mr. C. E. Love, Manager
Williamstown, W. Va.

Gentlemen:

Your notice of proposed well location
No. 1 on the B. F. Mayo Farm was received
May 31, 1934.

No objections have been filed in the
ten-day period subsequent to our receipt of your
notice. Drilling permit is hereby issued and
enclosed.

Very truly yours,

Chief of Department of Mines.

NPR:g

encl

01/05/2024

B-1

W00-27

WEST VIRGINIA DEPARTMENT OF MINES
 Oil and Gas Section
 PRELIMINARY DATA SHEET NO. 1

File No. Well No.

Burnt Hill Oil Company Company, of Williamstown

W. VA. on the B. F. Mayo Farm

containing 60 acres. Location Williams

..... District, in Wood County, West Virginia.

The surface of the above tract is owned in fee by B. F. Mayo

of Williamstown, W. Va. address, and the mineral rights are owned by

same of

The oil and gas privileges are held under lease by the above named company, and this well is drilled under permit No. W. 0027 issued by the West Virginia Department of Mines, Oil and Gas Section,

June 11, 1934

Elevation of surface at top of well, 500 feet U.S.G.S Spirit Barometric.

The number of feet of the different sized casings used in the well.

20 20 feet 10 in Casing size. Wood conductor

135 feet 8-1/4 size, csg. 900 feet 6-1/4 in sized csg.

..... feet..... size, csg..... feet..... sized csg.

..... feet..... size, csg..... feet..... sized csg.

..... packer of..... size, set at.....

..... packer of..... size, set at.....

..... in casing perforated at..... feet to..... feet.

..... in casing perforated at..... feet to..... feet.

Coal was encountered at none feet; thickness..... inches, and at.....

feet; thickness..... inches; and at..... feet; thickness..... inches.

Liners were used as follows: (Give details).....

.....

.....

Aug. 23, 1934 Date.

Approved Burnt Hill Oil Co Owner

By C. E. Love Manager (Title)

01/05/2024

AUG 25 1934

8/25/34

WEST VIRGINIA DEPARTMENT OF MINES

Oil and Gas Section

PRELIMINARY DATA SHEET NO. 1

File No. _____
Well No. _____
Burnt Hill Oil Company, Company of Williamsstown
on the _____
County, West Virginia
District in _____
The surface of the above tract is owned in fee by _____
of Williamsstown, Va. address and the mineral rights are owned by _____

The oil and gas privileges are held under lease by the above named company, and this well is drilled under permit No. _____ issued by the West Virginia Department of Mines, Oil and Gas Section, _____ June 11, 1934

U.S.G.S. Spirit Barometric _____
Elevation of surface at top of well _____ feet
The number of feet of the different sized casing used in the well _____

_____ feet _____ size _____ casing
_____ feet _____ size _____ casing
_____ feet _____ size _____ casing

_____ packer of _____ size set at _____
_____ packer of _____ size set at _____

_____ in casing perforated at _____ feet to _____ feet
_____ in casing perforated at _____ feet to _____ feet

Coal was encountered at _____ feet; thickness _____ inches and at _____ feet; thickness _____ inches

_____ layers were used as follows: (Give details) _____

Date _____

Approved _____
Owner

By _____
Manager (Title)

01/05/2024

AUG 27 1934

Burnt Hill Oil Company

COMPLETION DATA SHEET

Williamstown, W. VA. Address

NO. 2

#1. B. F. Mayo

Woo - 27

FORMATION RECORD

Name	Color	Character	Oil, Gas or Water	Top	Bottom	Thickness	Total Depth	Remarks
Red rock	red				100	100	100	20' - 10'
White Slate	or soapstone		Water - 125'	100	230	130	230	135' - 8 1/4"
Red Rock				230	300	70	300	
White shale				300	380	80	380	
Red rock				380	460	80	460	
White shale				460	495	35	495	
Red rock				495	600	105	600	
White muck				600	700	100	700	
Pink Rock				700	810	110	810	
Secend Cow Run Sand		broken	S. Water - 890'	810	900	90	900	900' - 6 1/4" ✓
White slate				900	920	20	920	
Sandy shale				920	960	40	960	
Maxburg Sand				960	978	18	978	
Black shale				978	1080	102	1080	
Salt Sand				1080	1136	55	1136	
White Slate				1136	1166	30	1166	
Black shale				1165	1185	20	1185	
Maxon Sand formation,		black shale		1185	1230	45	1230	
Maxon Sand				1230	1265	35	1265	
Black Shale				1265	1300	35	1300	
White slate				1300	1380	80	1380	
BIG INJUN SAND				1380	1417	37	1417	Dry hole

~~Shot~~
Well was not shot at not shot feet; well was shot at _____ feet.

~~Salt~~ Fresh water at 125 feet; ~~fresh~~ salt water at 890 feet.

Well was ~~producing~~ ~~hole~~ hole.
dry

Burnt Hill Oil Co.

August 23, 1934
Date

Approved by

C. E. Love

Owner

01/05/2024

NOTE: All bottom formations must be noted as indicated above and all key-rocks and oil and gas sands must be recorded under their proper geological names in the district as well as any local names commonly used in the district for such strata.

AUG 25 1934

COMPLETION DATA SHEET
NO. 2
FORMATION RECORD

Company Burnt Hill Oil
Address Williamstown, W. Va.

Remarks	Total Depth	Thickness	Bottom	Top	Oil Gas or Water	Character	Color	Name
	100	100	100				red	red rock
	230	130	230	100				White slate or soapstone
	300	70	300	230				Red rock
	380	80	380	300				White shale
	460	80	460	380				Red rock
	495	35	495	460				White shale
	600	105	600	495				Red rock
	700	100	700	600				White muck
	810	110	810	700				Pink Rock
	900	90	900	810		<u>broken</u>		<u>broken</u> Cow Run Sand
	930	30	930	900				White slate
	960	30	960	930				Sandy shale
	978	18	978	960				Maxon sand
	1080	102	1080	978				Black shale
	1135	55	1135	1080				salt sand
	1185	50	1185	1135				White shale
	1230	45	1230	1185				Black shale
	1285	55	1285	1230				Maxon sand formation, black shale
	1300	15	1300	1285				Maxon sand
	1380	80	1380	1300				Black shale
Dry hole	1417	37	1417	1380				White slate BIG TOWN SAND

Well was not shot at 1380 feet; well was shot at 1417 feet.
 Fresh water bit 1380 feet; ~~gas~~ water at 300 feet.
 Well was dry ~~productive~~ hole.
 Burnt Hill Oil Co.
 Approved by [Signature] Date August 22, 1934
 Owner

01/05/2024

NOTE: All bottom formations must be noted as indicated above and all key rocks and oil and gas sands must be recorded under their proper geological names in the district as well as any local names commonly used in the district for such strata.

B-9

PROPOSED MANNER OF PLUGGING AND FILLING WELL

(REQUIRED BY RULES AND REGULATIONS)

WEST VIRGINIA DEPARTMENT OF MINES

OIL AND GAS DIVISION

WORK ORDER

Well to be plugged and filled as follows:

WORK ORDER SUPPLIED BY THE DEPARTMENT OF MINES:

Bottom of well 1417'

Fill the hole with clay or other non-porous material from 1417' to 1360' - 20' above the Big Injun Sand.

Drive wood plug from 1360' to 1357'

Cement from 1357' to 1347' sealing the Big Injun Sand.

Continue to fill with clay from 1347' to 1165' - 20' above the Maxton Sand.

Drive wood plug from 1165' to 1162'

Fill with clay from 1162' to 1060' - 20' above the Salt Sand.

Drive wood plug from 1060' to 1057'

SET A PERMANENT BRIDGE AT 930' - 30' below the Second Cow Run Sand

Fill with clay to 903'

Drive wood plug from 903' to 900'

PULL 6 1/4" casing set at 900'

Continue to fill with clay from 900' to 790'

Drive wood plug from 790' to 787'

SET A PERMANENT BRIDGE AT 150'

Fill with clay from 150' to 138'

Drive wood plug from 138' to 135'

PULL 8 1/4" casing and

Fill with clay to the surface.

Erect a markersuch as is described in Rule 18, 1931 Regulations.

All be done in a workman-like manner.

To the Department of Mines,
Coal Owner or Operator,
Lease or Property Owner.

Gentlemen:

This "work order" is submitted for your approval and concurrence and unless notified of your disapproval or non-concurrence, the undersigned will proceed with the plugging and filling of said well in the above described manner on the date stated in the notice of intention to plug and abandon the said well on opposite side of this sheet.

Very truly yours,

Well Operator.

No objections have been filed by the coal owner or coal operator, or any available adjacent lease or property owners or interposed by the Department of Mines to the manner herein described for the plugging and filling of the well above mentioned. Therefore, the same is hereby approved this 27th day

of August, 1934

DEPARTMENT OF MINES
Oil and Gas Division

01/05/2024

By: _____

NOTE: This "work order" must be filed in duplicate, one copy for the files of the Department of Mines and the other to be approved or corrected and returned to the well operator as his authority for plugging said well.

B-8

Woo-27

FORM G-9

NOTICE OF INTENTION TO PLUG AND ABANDON WELL

(REQUIRED BY SECTION 9, ARTICLE 4, CHAPTER 22 OF THE CODE)

WEST VIRGINIA DEPARTMENT OF MINES

OIL AND GAS DIVISION

To THE DEPARTMENT OF MINES,
Charleston, W. Va.

B. F. Mayo, owner of land
COAL OPERATOR OR COAL OWNER

Burnt Hill Oil Company
NAME OF WELL OPERATOR

Williamstown, W. Va.
ADDRESS

Williamstown, W. Va.
COMPLETE ADDRESS

no coal
COAL OPERATOR OR COAL OWNER

August 23, 19 34

WELL TO BE ABANDONED

ADDRESS

Williams District

LEASE OR PROPERTY OWNER

Wood County

ADDRESS

Well No. 1

B. F. Mayo Farm

Gentlemen:—

The undersigned well operator is about to abandon the above described well and will commence the work of plugging and abandoning said well on the 28th day of August, 19 34, (which date shall not be less than five days after the day on which this notice so mailed is received, or in due course should be received by the Department of Mines).

This notice is given you in order that your respective representatives may be present at the plugging and filling of said well. You are further notified that whether you are represented or not represented the undersigned will proceed on that date, or shortly thereafter, to plug and fill said well in the manner required by Section 10, Article 4, Chapter 22 of the Code and given in detail on the reverse side of this notice, in "Work Order."

This notice is being mailed by registered mail to each of you at the above addresses on the above date.

Very truly yours,

Well Operator.


NOTE: Upon the abandonment of all wells drilled prior to June 1, 1929, a plat prepared by a competent engineer, showing the district and county in which the tract of land is located, the name and acreage of names of the owners of adjacent tracts, and the location of the about to be abandoned well, determined by survey, and the courses and distances of such well from two permanent points or landmarks on said tract, shall be submitted with this notice.

(Over)

01/05/2024

PLAT OF THE PROPOSED LOCATION OF WELL NO. 1 OF THE BURNT HILL OIL COMPANY OF WILLIAMSTOWN, WEST VIRGINIA, ON THE B. F. MAYO FARM, CONSISTING OF 60 ACRES, LOCATED IN WILLIAMS DISTRICT, WOOD COUNTY, WEST VIRGINIA.

ELLA McDOUGLE



ENGINEER'S CERTIFICATE

I, THE UNDERSIGNED, HEREBY CERTIFY THAT THIS MAP IS CORRECT, AND SHOWS ALL THE INFORMATION, TO THE BEST OF MY KNOWLEDGE AND BELIEF, REQUIRED BY THE OIL AND GAS SECTION OF THE MINING LAWS OF WEST VIRGINIA.

J. E. Anderson
SURVEYOR
PARKERSBURG, W. VA.

ACKNOWLEDGED BEFORE ME, A NOTARY PUBLIC IN AND FOR WOOD COUNTY, WEST VIRGINIA, THIS 26 DAY OF MAY, 1934.

W. H. Ferry
NOTARY PUBLIC

MY COMMISSION EXPIRES ON THE 17th DAY OF May 1940

10/05/2024
Wood 21