

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: M. E. Davis ETAL Operator Well No.: M-499  
LOCATION: Elevation: 1360.14' Quadrangle: Cameron 7.5'  
District: Liberty County: Marshall  
Latitude: 39.790441 Feet South of 39 Deg. 47 Min. 25.6 Sec.  
Longitude: 80.592818 Feet West of 80 Deg. 35 Min. 34.1 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company West Virginia Land Resources, LLC. Coal Operator West Virginia Land Resources, LLC.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent Jay Hores Coal Operator \_\_\_\_\_  
Permit Issued Date 2/26/2026 or Owner \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Marshall ss:

Matthew A. Yearsley and Ethan Lucas being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 2nd day of June, 2026, and the well was plugged and filled in the following manner:

| TYPE                                     | FROM  | TO      | PIPE REMOVED      | LEFT  |
|------------------------------------------|-------|---------|-------------------|-------|
| Prestope Cement + Green Dyed Gas Blocker | 1310' | 833'    | 7" Casing 0'      | 2184' |
| Expandable Cement                        | 833'  | Surface | 8 5/8" Casing 0'  | 1132' |
|                                          |       |         | 10 3/4" Casing 0' | 320'  |
|                                          |       |         | 16" Conductor 0'  | 20'   |
|                                          |       |         |                   |       |
|                                          |       |         |                   |       |
|                                          |       |         |                   |       |

Description of monument: 77' of 7" casing with Company Name, Well#, API#, and date cemented and that the work of plugging and filling said well was completed on the 11th day of June, 2026.

And further deponents saith not. Matthew A Yearsley  
Ethan Lucas



Sworn and subscribe before me this 21<sup>st</sup> day of July, 2024  
My commission expires: August 13, 2029 Kerri A McCormick  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Strader Gower Title: Oil & Gas Inspector

08/07/2026

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

WEST VIRGINIA LAND RESOURCES INC  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

BYARD - CLEMENT FAMILY TRUST  
Lease or Property Owner  
323 Sunset LN., Glen Dale, WV 26038  
Address

WEST VIRGINIA LAND RESOURCES INC  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address

Cameron, WV 7.5'  
Well Location

Liberty

District

Marshall

County

M-499

Well No.

M. E. DAVIS ETAL  
Farm

RECEIVED  
Office of Oil and Gas

AUG 03 2026

WV Department of  
Environmental Protection

STATE INSPECTOR SUPERVISING PLUGGING Strader Gower

*Strader Gower*  
AFFIDAVIT  
7/21/2026


STATE OF WEST VIRGINIA,  
County of Marshall ss:

MATTHEW A. YEARSLEY and Ethan Lucas being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources LLC well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 2nd day of June 2026 and that the well was plugged in the following manner:

| Sand or Zone<br>Record                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Filling Material | Casing/Tubing Size                                                                                                                                               | Casing<br>Pulled | Casing<br>Left In |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|-------------------|
| Formation                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                  |                                                                                                                                                                  |                  |                   |
| Cleaned inside the 7" casing from surface to 1310'. Made a diligent attempt to remove the 7" casing by pulling 150% of the string weight. All attempts were unsuccessful. Left 2184' of 7" casing from surface to 2184'. Left 1132' of 8 5/8" casing from surface to 1132'. Made cuts through both the 7" and 8 5/8" casings at the following depths: 1240', 1190', 1090', 1041', 1040', 1038.5', 1037', 1035.5', 1034', and 1032.5'. Placed cuts in 7" casing at 1240' and 1196'. Pittsburgh Coal Seam was located from 1033' to 1040'. Due to the extreme cement bonding behind the 7" and 8 5/8" casing, no additional cuts, rips or perforations were required. | 7" Casing        | 0'                                                                                                                                                               | 2184'            |                   |
|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 8 5/8" Casing    | 0'                                                                                                                                                               | 1132'            |                   |
|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 10 3/4" Casing   | 0'                                                                                                                                                               | 320'             |                   |
|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 16" Conductor    | 0'                                                                                                                                                               | 20'              |                   |
| <u>Cemented the hole from 1310' to surface as follows:</u><br>From 1310' to 833' using 110 sacks of Thixotropic Cement with a Green Dye and Gas Blocker additive. From 833' to surface using 160 sacks of Expandable Cement. Left 2184' of 7" casing from surface to 2184' to surface. Left 1132' of 8 5/8" casing from surface to 1132'. A total of 270 sacks of cement were used to cement the hole from 1310' to surface. Cement circulated back to surface. Left 320' of 10 3/4" casing from surface to 320'. Left 20' of 16" conductor from surface to 20'.                                                                                                    |                  |                                                                                                                                                                  |                  |                   |
| Coal Seams                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                  | Description of Monument                                                                                                                                          |                  |                   |
| Pittsburgh                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 1033' to 1040'   | 77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level. |                  |                   |
|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                  |                                                                                                                                                                  |                  |                   |
|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                  |                                                                                                                                                                  |                  |                   |

... and that the work of plugging and filling said well was completed on the 11<sup>th</sup> day of June 2026

And further deponents saith not



Sworn to and subscribed before me this 21<sup>st</sup> day of July 2026

Matthew A Yearsley

Matthew A. Yearsley

Ethan Lucas

Ethan Lucas

*Kerri McCormick*  
Notary Public

My commission expires:

August 13, 2029

Permit No. 47-051-00053-00-00

Well No. M-499

Latitude: 39° 47' 25.6" N

Longitude: -80° 35' 34.1" W

08/07/2026