

New Location
 Drill Deeper
 Abandonment

Surface = F.D. Jones
 R.# 2, Fairview W Va
 Coal = ~~Mountain State Coal~~
~~West Virginia~~
~~Fairview W. Va.~~

Company Natural Gas of W. Va. Inc.
 Address Box 124 Burton, W. Va.
 Farm F. D. Jones
 Tract 025 Acres 60 Lease No. _____
 Well (Farm) No. 2 Serial No. _____
 Elevation (Spirit Level) 1099
 Quadrangle Blairsville, Wc
 County Morgania District Clay
 Engineer A. L. Headley
 Engineer's Registration No. 2022
 File No. _____ Drawing No. _____
 Date 6-18-1961 Scale 20 poles / inch

STATE OF WEST VIRGINIA
 DEPARTMENT OF MINES
 OIL AND GAS DIVISION
 CHARLESTON

WELL LOCATION MAP
 FILE NO. MON-253-P

+ Denotes location of well on United States Topographic Maps, scale 1 to 62,500, latitude and longitude lines being represented by border lines as shown.
 - Denotes one inch spaces on border line of original tracing.



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION 9

Quadrangle Blacksville

WELL RECORD

Permit No. Mon-253

Oil or Gas Well Oil
(KIND)

Company Natural Gas of W. Va. Inc.
Address Box 124
Farm B. D. Jones Acres 60
Location (waters) Benefield
Well No. 2 Elev. 1079
District Clay County Monongalia
The surface of tract is owned in fee by F. D. Jones
Address _____
Mineral rights are owned by Jones Heirs
Fairview, Address West Virginia
Drilling commenced July 26, 1961
Drilling completed October 22, 1961
Date Shot None From _____ To _____
With None
Open Flow /10ths Water in None Inch
/10ths Merc. in _____ Inch
Volume None Cu. Ft.
Rock Pressure None lbs. _____ hrs.
Oil (15) bbls., 1st 24 hrs.
WELL ACIDIZED No
WELL FRACTURED No


Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			
13	117	117	
10	856	856	Size of
8 1/4	1234	1234	
6 5/8	1868	1868	Depth set
5 3/16			
3			Perf. top
2	2224	2224	Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED 10 SIZE 856 No. Ft. _____ Date _____

COAL WAS ENCOUNTERED AT 465 FEET _____ INCHES
742 FEET _____ INCHES 818 FEET _____ INCHES
_____ FEET _____ INCHES _____ FEET _____ INCHES

RESULT AFTER TREATMENT None
ROCK PRESSURE AFTER TREATMENT None *465*
Fresh Water 16-40; 75-80; 736-742, Salt Water 1716; 1769; 1789 Feet

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Clay	Light	Soft	0	12			
Rock	Light	Hard	12	16			
Red Rock	Red	Soft	16	40			
Slate	Dark	Soft	40	60			
Red Rock	Red	Soft	60	70			
Lime	Light	Hard	70	80			
Slate	Dark	Soft	80	95			
Lime	Light	Hard	95	100			
Slate	Light	Soft	100	130			
Red Rock	Red	Soft	130	137			
Slate	Light	Soft	137	155			
Lime	Light	Hard	155	190			
Slate & Shells	Light	Hard	190	285			
Lime	Light	Hard	285	310			
Slate & Shells	Light	Hard	310	382			
Lime	Light	Hard	382	420			
Bluff Sand	Light	Hard	420	455			
Slate	Light	Soft	455	465			
Coal	Dark	Hard	465	468			
Slate & Shells	Light	Hard	468	500			
Lime	Light	Hard	500	535			
Slate & Shells	Light	Hard	535	570			
Lime	Light	Hard	570	585			
Slate & Shells	Light	Hard	585	625			
Lime	Light	Hard	625	638			
Slate & Shells	Light	Hard	638	650			
Lime	Light	Hard	650	736			
Coal Sew	Dark	Hard	736	742			



Formation	Color	Hard or Soft	Top ⁹	Bottom	Oil, Gas or Water	Depth Found	Remarks
Lime	Light	Hard	742	755			
Slate	Dark	Hard	755	765			
Lime	Light	Hard	765	812			
Slate	Dark	Hard	812	818			
Coal ^{Fgh}	Black	Hard	818	824			
Lime	Light	Hard	824	854			
Slate	Dark	Hard	854	910			
Lime	Light	Hard	910	925			
Slate	Dark	Hard	925	938			
Lime	Light	Hard	938	950			
Red Rock	Red	Soft	950	955			
Lime	Light	Hard	955	965			
Slate	Dark	Hard	965	995			
Red Rock	Red	Soft	995	1005			
Slate	Dark	Hard	1005	1055			
Lime	Light	Hard	1055	1075			
Slate	Dark	Hard	1075	1147			
Sand	Light	Hard	1147	1168	Show of oil	1150	
Slate	Dark	Hard	1168	1185			
Shale	Dark	Soft	1185	1190			
Slate	Dark	Hard	1190	1260			
Sand	Light	Hard	1260	1276			
Slate	Dark	Hard	1276	1292			
Lime	Light	Hard	1292	1312			
Slate	Dark	Hard	1312	1328			
Sand	Light	Hard	1328	1360			
Slate	Dark	Hard	1360	1383			
Sand	Light	Hard	1383	1405			
Slate	Dark	Hard	1405	1413			
Sand	Light	Hard	1413	1450			
Slate	Dark	Hard	1450	1532			
Sand	Light	Hard	1532	1585			
Slate	Dark	Hard	1585	1626			
Sand	Light	Hard	1626	1665			
Slate	Dark	Hard	1665	1695			
Salt Sand	Light	Hard	1695	1771			
Lime	Light	Hard	1771	1778			
Sand	Light	Hard	1778	1875			
Slate	Dark	Hard	1875	1902			
Lime & Slate	Medium	Hard	1902	1950			
Red Rock	Red	Soft	1950	2015			
Little Lime	Light	Hard	2015	2077			
Pencil Cave	Dark	Soft	2077	2086			
Big Lime	Light	Hard	2086	2160			
Big Injun ³⁷¹	Light	Hard	2160	2224	Oil at 2214	2218	
Sand	Light	Hard	2224	2234			
				Total Depth	2234		

Date May 26, 1962
APPROVED Natural Gas of Iowa, Inc. Owner
By Franklin R. Yost, Pres.
(Title)