

Rev (5-01)
WR-38
DATE: 01-06-10

API # 47-6101592P

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Perkey, Arlyn Operator Well No.: F2- S-4
LOCATION: Elevation: 1,336' Quadrangle: Blacksville
District: Clay County: Monongalia
Latitude: 11,308' Feet South of 39 Deg. 40 Min. 00 Sec.
Longitude: 7,161' Feet West of 80 Deg. 12 Min. 30 Sec.
Well Type: OIL GAS
Company: Eastern Associated Coal LLC Coal Operator: Eastern Associated Coal LLC
1044 Miracle Run Road or Owner 1044 Miracle Run Road
Fairview, WV 26570 Fairview, WV 26570
Agent: Edward Y. Hoy Coal Operator or Owner

Permit issued Date: January 28, 2009

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Hermitton Gump and William J Stonking being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Tristan Jenkins, Oil and Gas Inspector representing the Director, say that said work was commenced on the 13th day of August, 2009, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
	Cleaned out with 9 5/8" bit to 915'. Cleaned out with 8 3/4" bit to 1,271'.			
	Logged the hole with Century Wireline Service. Coal seam 947' to 954' based on log information. The hole deviated 6.1 feet at the coal seam.			
	Ran 1-1/2" tubing and pumped the bottom plug with 100 sacks of E1K expanding cement. The top of the bottom plug is 1058' deep.			
	Ran 1,058' of 4-1/2" tubing and pumped the top plug with 800 sacks of E1K expanding cement. Swabbed water off hole. Latch down plug at 1,016'.			

Description of monument: 4 1/2" Pipe with metal plate, API #, and date plugged and that the work of plugging and filling said well was completed on the 10th day of October, 2009.

And further deponents saith not. Hermitton Gump


William J Stonking

Sworn and subscribe before me this 6th day of January, 2010

My commission expires: July 7, 2014

[Signature]
Notary Public

Oil and Gas Inspector: [Signature]



RECEIVED
Office of Oil & Gas

JUN 12 2012

WV Department of
Environmental Protection

06/22/2012