

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Prout, Alfred H. JR. Operator Well No.: WV605428 (Highland & Barr)

LOCATION: Elevation: 960' Quadrangle: Big Run
District: Grant County: Wetzel
Latitude: _____ Feet South of _____ Deg. _____ Min. _____ Sec.
Longitude: _____ Feet West of _____ Deg. _____ Min. _____ Sec.

Well Type: OIL _____ GAS X

RECEIVED
Office of Oil & Gas

Company EQT Production Company Coal Operator Consolidation Coal Company
1710 Pennsylvania Avenue or Owner 1000 Conso Energy DR
Charleston, WV 25302 Canonsburg, Pa. 15317 NOV 14 2013

Agent Rex C. Ray Coal Operator ATTN: Don Puglio WV Department of
Permit Issued Date 7-16-2012 or Owner WPP LLC Environmental Protection
5260 Irwin Rd, Huntington, WV 25705 ATTN: George Angus

AFFIDAVIT

STATE OF WEST VIRGINIA, KY
County of Floyd ss:

Charles Moore and Rodney Osborne being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 31st day of July, 2013, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
See Attachment A			288' of 8 1/4"	288' of 10"
			998' of 6 5/8"	1233' of 8 1/4"
				980' of 6 5/8"
				Perfd 3 holes each @ 507', 707', 507', 507', 495', 350', 296',
				250', 216', 100', 50'. Perfd 6 holes each @ 757', 645', 430', 420'


Description of monument: 4" casing w/ plug date and API # 36" above ground and that the work of plugging and filling said well was completed on the 12th day of August, 2013.

And further deponents saith not. Charles Moore
Rodney Osborne

Sworn and subscribe before me this 15th day of August, 2013

My commission expires: 9-26-14

Michelle Handshoe
Notary Public



Affidavit reviewed by the Office of Oil and Gas: _____ Title: 10/25/13 11/22/2013

Highland Barr 605428
Attachment A

103.00289

<u>Type</u>	<u>From</u>	<u>To</u>
6% Gel	2372'	Surface
Class A Cement	2370'	2255'
Class A Cement	2047'	1855'
Class A Cement	1575'	1298'
Class A Cement	1228'	1109'
Class A Cement	1071'	938'
Class A Cement	819'	585'
Class A Cement	504'	205'
Class A Cement	126'	Surface