

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: J. W. Norris #4 Operator Well No.: 7391
LOCATION: Elevation: 1161.62' Quadrangle: Big Run, WV 7.5'
District: Grant County: Wetzel
Latitude: 39.52402 Feet South of 39 Deg. 31 Min. 26.5 Sec.
Longitude: 80.51664 Feet West of 80 Deg. 30 Min. 59.9 Sec.

RECEIVED
Office of Oil and Gas

AUG 03 2026

WV Department of
Environmental Protection

Well Type: OIL ☒ GAS ☐

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 3/2/2026 or Owner _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Wetzel ss:

Matthew A. Yearsley and Brad Thrasher being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 20 th day of May, 2026, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable Cement	2330'	1150'	5/8" Sucker Rod 2295'	0'
Expandable Cement	1150'	742'	2 3/8" Tubing 2300'	0'
Expandable Cement	742'	Surface	5 1/2" Casing 2225'	30'
			7" Casing 0'	Unknown
			16" Conductor 0'	15'

Description of monument: 77" of 7" casing with Company Name, Well#, API#, and date cemented and that the work of plugging and filling said well was completed on the 11 th day of June, 2026.

And further deponents saith not. Matthew A Yearsley
Brad Thrasher



Sworn and subscribe before me this 16 th day of July, 2026

My commission expires: August 13, 2029
Kerri McCormick
Notary Public
Digitally signed by Stephen Mccoy
Mccoy
Date: 2026.07.19 21:57:35 -04'00'

Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____

08/07/2026

FORM WR-38
(Affidavit of Plugging)

WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OIL AND GAS WELLS DIVISION

AUG 03 2026

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES INC
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
TALL TIMBER INC
Lease or Property Owner
4464 Mannington Rd, Smithfield, WV 26437
Address

WEST VIRGINIA LAND RESOURCES INC
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
Big Run, WV 7.5'
Well Location
GRANT
District
WETZEL
County
7391
Well No.
J. W. NORRIS #4
Farm


STATE INSPECTOR SUPERVISING PLUGGING Steve McCoy Stephen McCoy Digitally signed by Stephen McCoy
Date: 2026.07.19 21:57:48 -04'00'

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Wetzel ss:
MATTHEW A. YEARSLEY and Brad Thrasher being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources Inc well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 20th day of May 2026 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Pulled all 2295' of 5/8" sucker rod from surface to 2295'. Pulled all 2300' of 2 3/8" tubing from surface to 2300'. Cleaned 4 3/4 " hole to 2330'. Cut 5 1/2" casing at 2225' and removed from surface to 2225'. Left 30' of 5 1/2" casing from 2225' to 2255'. Left an unknown amount of 7" casing from surface to an unknown depth. Perforated the 7" casing at 1750', 1650', 1550', 1450', 1350', and 1250'. Made a cut in the 7" casing at 959.7'. Made a diligent attempt to pull the 7" casing by pulling 150% of the string weight. All attempts were unsuccessful. Perforated the 7" casing with 6 shorts each at 1149.7', 1099.7', 1049.7', and 999.7'. Placed cuts at the 7" casing at 954.7', 949.7', 947.7', 945.7', 943.7', 942', 937', 932', 892', and 842'. Cleaned a 6 1/4" hole through the Pittsburgh Coal Seam from 942' to 949.7'. Cemented the hole from 2330' to 1150' using 220 sacks of Expandable Cement.	5/8" Sucker Rod	2295'	0'	
	2 3/8" Tubing	2300'	0'	
	5 1/2" Casing	2225'	30'	
	7" Casing	0'	Unknown	
	16" Conductor	0'	15'	
<u>Cemented the hole from 1150' to surface as follows:</u> From 1150' to 742' using 85 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. From 742' to surface using 150 sacks of Expandable Cement. A total of 455 sacks were used to cement the hole from 2330' to surface. Cement did circulate at surface. Left 15' of 16" conductor pipe from surface to 15'.				
Coal Seams		Description of Monument		
Pittsburgh	942' to 949.7'	77' of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 11th day of June 2026



Sworn to and subscribed before me this 16th day of July 2026

My commission expires:
August 13, 2029

Matthew A Yearsley

Matthew A. Yearsley

Brad Thrasher

Brad Thrasher

Kerri A McCormick
Notary Public

Permit No. 47-103-01077-00-00
Well No. 7391
Latitude: 39° 31' 26.5" N
Longitude: -80° 30' 59.9" W

08/07/2026