

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: H.L. Smith Operator Well No.: 7220

LOCATION: Elevation: 900.73' Quadrangle: FOLSOM WV 7.5'  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 29 Min. 26.38314 Sec.  
Longitude: \_\_\_\_\_ Feet West of 80 Deg. 32 Min. 25.24424 Sec.

Well Type: OIL \_\_\_\_\_ GAS \_\_\_\_\_

Company Consolidation Coal Co. Coal Operator 1 Bridge Street Monongah, WV 26554  
or Owner \_\_\_\_\_  
Agent David Roddy Coal Operator \_\_\_\_\_  
or Owner \_\_\_\_\_  
Permit Issued Date 04/23/2019

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Kevin S. Wright and Matthew A. Yearsley being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 16th day of March, 2020, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic w/ Green Dye	933'	486'		
Expandable Cement	486'	Surface		
8 5/8" casing	824'	Unknown	85'	Unknown

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 27th day of March, 2020.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 6<sup>th</sup> day of Apr, 2020  
My commission expires: 09/15/22  
[Signature]  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Derek M. Haught Title: Oil & Gas Inspector

# Plugging Report for MSHA

Well Number: 7220

Mine: Harrison County Mine

Surface

Permit Number: 47-103-03291

Date Clean Out Started: 3/16/2020

Date Well Bore Plugged: 3/27/2020

Pittsburgh Coal Seam: 686 ft. To 694 ft.

**Plugs:**

From	To	Type of Cement
933'	486'	Thixotropic Cement w/ Green Dye
486'	Surface	Expandable Cement

**Casing Remaining in Well Bore**

Thix Top: 486'

	Top	Bottom	Left	Pulled
Sucker Rods				
2 3/8" tubing				
4 1/2" casing				
7" casing				
7" fiberglass				
8 5/8" casing	824'	Unknown	Unknown	85'
10 3/4" casing				
16" Conductor				

Expandable Cement

Thixotropic Cement w/  
Green Dye

686' - 694'

Pittsburgh Coal

Thixotropic Cement w/  
Green Dye

Top of 8 5/8" Casing at 824'

Thix Bottom: 933'

Bottom of 8 5/8" casing unkno

**Cement:**

Expandable	<u>340</u>	sacks
Thixotropic	<u>300</u>	sacks
Econofill		sacks
Mud Flush	<u>1000</u>	gal
Other		
Est. Top Thix		ft
Did Cement Circ.	<u>YES</u>	

**Comments:**

Caving: Extreme Moderate Normal

Lost Circulation: Extreme Moderate Normal

Difficulty in Removing Casing: Extreme Moderate Normal

Debris in Well Bore: Wood Steel Other: \_\_\_\_\_

Surface Elevation (Surveyed)	<u>886'</u>
Bottom of Coal Structure (Map)	<u>225'</u>
Difference	<u>661</u>

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
AMANDA DANIELLE TRADER  
Lease or Property Owner  
315 STOUT RUN RD. SMITHFIELD, WV 26437  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
FOLSOM, WV 7.5'  
Well Location  
GRANT  
District  
WETZEL  
County  
7220  
Well No.  
H.L. SMITH  
Farm

STATE INSPECTOR SUPERVISING PLUGGING

*Derek M. Haught*

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

**KEVIN S. WRIGHT** and **MATTHEW A. YEARSLEY** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 16<sup>TH</sup> day of March, 2020 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
	Cleaned hole with a 12 1/4" bit from surface to 328'. Reduced hole to 9 7/8" bit at 328'. Cleaned hole with a 9 7/8" bit from 328' to 824' to top of 9 5/8" casing. Reduced hole to 7 7/8" bit at 824'. Cleaned a hole with 7 7/8" bit from 824' to 933'. Tagged plug at 933'. Removed 85' of 8 5/8" casing from 824' to 909'. Left an unknown amount of 8 5/8" casing from 909' to an unknown depth. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam from 686' to 694'.  <b>Cemented from 933' to surface as follows:</b> From 933' to 486' with 265 sacks of Thixotropic Cement with Green Dye. Tagged cement plug at 546'. Cemented from 546' to 486' with 35 sacks of Thixotropic Cement. From 248' to surface with 340 sacks of Expandable Cement. Cement did circulate at surface. Left 20' of 16" conductor from surface to 20' in wellbore.	8 5/8" Casing	85'	Unknown
<b>Coal Seams</b>		<b>Description of Monument</b>		
<b>Pittsburgh</b>	686' - 694'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 27<sup>th</sup> day of March, 2020

And further deponents saith not.

*Kevin S. Wright*


Kevin S. Wright

*Matthew A. Yearsley*

Matthew A. Yearsley

Sworn to and subscribed before me this *6<sup>th</sup>* day of *Apr 2020*

*[Signature]*  
Notary Public



Permit No. 47-103-03291  
Well No. 7220  
Latitude: 39° 29' 26.38314"N  
Longitude: 80° 32' 25.24424"W