

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: B. W. Peterson Operator Well No.: 7275

LOCATION: Elevation: 1170.15' Quadrangle: Big Run WW  
District: Grant County: Wetzel  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 30 Min. 02.26 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 31 Min. 36.65 Sec.

Well Type: OIL X GAS \_\_\_\_\_

Company West Virginia Land Resources, Inc. Coal Operator West Virginia Land Resources, Inc.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
or Owner \_\_\_\_\_  
Permit Issued Date 03/07/2022


AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 4th day of May, 2022, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thotropic w/ Green Dye and Gas Block	1194'	783'		
Expandable Cement	783'	Surface		
8 5/8" Casing	959'	Unknown	0'	Unknown
16" Conductor	Surface	13'	0'	13'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 27th day of May, 2022.



Matthew A. Yearsley  
Kevin S. Wright

Sworn and subscribed before me this 14th day of Jun, 2022  
My commission expires: 09/15/22  
Notary Public

RECEIVED  
Office of Oil and Gas  
JUN 24 2022  
WV Department of  
Environmental Protection

Affidavit reviewed by the Office of Oil and Gas: Kenneth Greynolds Digitally signed by Kenneth Greynolds  
DN: CN = Kenneth Greynolds email = Kenneth.L.Greynolds@wv.gov C = AD O = WV DEP OU = Oil and Gas  
Date: 2022.06.21 09:33:05 -0400 Title: \_\_\_\_\_

WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OIL AND GAS WELLS DIVISION

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
WEST VIRGINIA LAND RESOURCES INC.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
COASTAL FOREST RESOURCES CO.  
Lease or Property Owner  
P.O. BOX 1023, HAVANA, FL 32333  
Address

WEST VIRGINIA LAND RESOURCES INC  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
BIG RUN W.VA  
Well Location  
GRANT  
District  
WETZEL  
County  
7275  
Well No.  
B. W. PETERSON  
Farm

STATE INSPECTOR SUPERVISING PLUGGING Kenneth Greynolds

Digitally signed by Kenneth Greynolds  
DN: cn = Kenneth Greynolds, email = Kenneth.L.Greynolds@wv.gov, c = AD, o = WVDOG, ou = Oil and Gas  
Date: 2022.05.21 08:53:58 -0400

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MATTHEW A. YEARSLEY and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, Inc. well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 4<sup>th</sup> day of May, 2022 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned the hole with 12 1/4" bit from the surface to 180'. Reduced the hole to 9 7/8" at 180'. Cleaned the hole with 9 7/8" bit from 180' to the top of the existing 8 5/8" casing at 959'. Reduced the hole to 6 1/4" at 959'. Cleaned out the 8 5/8" casing with a 6 1/4" bit from 959' to 1194'. Cleaned a 6 1/4" through the Pittsburgh Coal Seam (983.0' to 990.2'). Cut the 8 5/8" casing at 1000.2'. Attempted to pull 8 5/8" casing from 959' to 1000.2' by pulling 150% of string weight but all attempts were unsuccessful. Additional cuts were placed in the 8 5/8" casing at 1190.2', 1140.2', 1090.2', 1040.2', 1000.2', 995.2', 990.2', 988.2', 986.2', 984.6', 983', 978', 973'. Left an unknown amount of 8 5/8" casing in the hole from 959' to an unknown depth. Left 13' of 16" conductor in hole from the surface to 13'.		8 5/8" Casing	0'	Unknown
		16" Conductor	0'	13'
<b>Cemented the hole from 1194' to surface as follows:</b> From 1194' to 783' with 165' sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. From 783' to surface using 430 sacks of Expandable Cement. Cement did circulate at surface. A total of 595 sacks of cement were used to fill the hole from 1194' to the surface.				
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	983.0' – 990.2'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 27th day of May, 2022

And further deponents saith not.



Sworn to and subscribed before me this 14<sup>th</sup> day of Jun, 2022

Matthew A. Yearsley

Matthew A. Yearsley

Kevin S. Wright

Kevin S. Wright

[Signature]  
Notary Public

My commission expires: 09/15/22

Permit No. 47-103-03489  
Well No. 7275  
Latitude: 39° 30' 02.26"N  
Longitude: -80° 31' 36.65"W

RECEIVED  
Office of Oil and Gas

JUN 24 2022

WV Department of  
Environmental Protection

02/23/2024

...

...

...

...

...

...

...

...

...

...

...

...

...

...

CONFIDENTIAL - SECURITY INFORMATION

2203 A S 100

CONFIDENTIAL - SECURITY INFORMATION