



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

1195

WELL RECORD

Oil or Gas Well _____ (KIND)

Permit No. AP 1195


Company The Manufacturers Light & Heat Co.
Address 800 Union Trust Bldg., Pittsburgh, Pa.
Farm Mary A. Teagarden Acres 155
Location (waters) _____
Well No. 2137 Elev. _____
District Church County Wetzel
The surface of tract is owned in fee by Cora Elisabeth Teagarden, et al Address Hundred, W. Va.
Mineral rights are owned by The Mfrs. Light & Heat Co.
800 Union Trust Bldg. Address Pittsburgh, Pa.
Drilling commenced July 10, 1917
Drilling completed September 20, 1917
Date Shot _____ From _____ To _____
With _____
Open Flow _____ /10ths Water in _____ Inch
_____ /10ths Merc. in _____ Inch
Volume _____ Cu. Ft.
Rock Pressure _____ lbs. _____ hrs.
Oil _____ bbls., 1st 24 hrs.
Fresh water _____ feet _____ feet
Salt water _____ feet _____ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer _____
16			
13			
10	291	59	Size of <u>6-5/8" x 1/4"</u>
8 1/4	1524-9	NONE	
6 1/2	2228-1	2228-1	Depth set <u>2240</u>
5 3/16			
3			Perf. top _____
2			Perf. bottom _____
Liners Used			Perf. top _____
			Perf. bottom _____

CASING CEMENTED _____ SIZE _____ No. Ft. _____ Date _____

COAL WAS ENCOUNTERED AT 935 FEET 60 INCHES
1035 FEET 84 INCHES FEET INCHES
FEET INCHES FEET INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Mapletown Coal			935	940			
Pittsburgh Coal			1035	1042			
Little Dunkard Sand			1125	1176	Gas at 1130 ft.		
Big Dunkard Sand			1505	1550	Gas at 1515 ft.		
Gas Sand			1680	1704			
First Salt Sand			1825	1850	Gas at 1842 ft.		
Second Salt Sand			1853	1890	Water at 1845 ft to 1849 ft.		
Third Salt Sand			1894	2010			
Pencil Cave			2223	2225			
Big Lime			2225	2305	6-5/8" Casing set at 2228'		
Big Injun Sand			2305	2500	Gas at 2377		
Sand			2595	2645			
Sand			2868	2880			
Fifty Foot Sand			2975	2995	Show of oil at 2980		
Thirty Foot Sand			3080	3100			
Gordon Sand			3144	3183	Show of oil 3172		
Fourth Sand			3189	3193	Gas 3189 to 3193, test 7/10 mercury		
Sand			3210	3226	in a 3" opg. blown down to 23/10 mercury in a 2" opening.		
TOTAL DEPTH				3266			



Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks

Date JULY 31, 19 51

APPROVED THE MANUFACTURERS LIGHT & HEAT CO., Owner

By *P. S. Cooper* LAND AGENT.
(Title)